




บริษัท อีควิตี้ เซอร์วิสเชส แอนด์ โซลูชั่นส์ จำกัด
801/138 หมู่8 ถนนพหลโยธิน
ต.คูคต อ.ลำลูกกา จังหวัดปทุมธานี 12130.
โทร. 0 2992 5040 โทรสาร 0 2992 5041
โทร. 0 2998 7308 โทรสาร 0 2998 7309
อีเมล : esspower@esspower.com
manorom@bteng.com

Equity Services & Solutions Co., Ltd
801/138 Moo 8 Phaholyothin Rd.,
Ku-Kod, Lamluka, Prathumthanee12130
Tel : 0 2992 5040, Fax : 0 2992 5041
Tel : 0 2998 7308, Fax : 0 2998 7309
Email : esspower@esspower.com
manorom@bteng.com

Turbo-compressor

TEK-3200/3300/3400

RCM study



Reported by Santi Songkunlertchai
Manorom Chiewpanich
Equity Services & Solutions Co., Ltd

Project Ref No : 07-10-

Date 28 Oct 2007



บริษัท อีควิตี้ เซอร์วิสเชส แอนด์ โซลูชั่นส์ จำกัด
801/138 หมู่8 ถนนพหลโยธิน
ต.คูคต อ.ลำลูกกา จังหวัดปทุมธานี 12130.
โทร. 0 2992 5040 โทรสาร 0 2992 5041
โทร. 0 2998 7308 โทรสาร 0 2998 7309
อีเมล : esspower@esspower.com
manorom@bteng.com

Equity Services & Solutions Co., Ltd
801/138 Moo 8 Phaholyothin Rd.,
Ku-Kod, Lamluka, Prathumthanee12130
Tel : 0 2992 5040, Fax : 0 2992 5041
Tel : 0 2998 7308, Fax : 0 2998 7309
Email : esspower@esspower.com
manorom@bteng.com

Contents

1. Summary
2. Introduction
3. Work scope
4. Details
5. Maintainable item and interval and maintenance technique
6. Manpower and Resources
7. Attachments

8.

1. Summary

The summary below indicates the major findings only.

- 1.1 It is found that the current job card is not full-fill the maintenance activities. Job card shall drilldown to activities and maintenance item level (sub-skid level) as per the result of this RCM.
- 1.2 Online washing should be introduced to Gas Producer in order to extend the crank wash interval.
- 1.3 To eliminate wax-gum cumulative at dry gas seal, the source of “buffer gas” shall be off-taken from the final discharge downstream of the after cooler.
- 1.4 Dry gas seal replacement interval shall be extended and based on “condition base” instead of “time base”.
- 1.5 Online washing should be introduced to “compressor”. Rigorous study shall be conducted to prevent “dry gas seal” damage during on-line wash.
- 1.6 Power augmentation should be introduced to gain the gas export.
- 1.7 Anti-surge function shall be tested-stimulated as regular basis.
- 1.8 To increase the system availability, “TT-3320” function should be changed from “shutdown” to “alarm” only.
- 1.9 Each compression string, it is found that the total maintenance cost with lost time for maintenance will be 76 million Baht per year
- 1.10 Each compression string, it is found that the minimum total production lost with out maintenance will be 487 million Baht per year, Maximum: 8000 million Baht per year
- 1.11 It can pointed that the average recovery time from breakdown should be 12 hours at the lost of revenue at 25% of each of gas compression string.

Cost from maintenance activities	76 231 593	Baht per year	with product lost (parts included)
Min production lost w/o maintenance	487 142 857	Baht per year	
Max breakdown cost with production lost	8 035 535 410	Baht per year	
RAM	2	A 0,5	

2. Introduction

This report was made according the PTTEP Service Order No.....to conduct the RCM study using the combination of FMEA* (Failure Mode Effective Analysis) technique and FMECA* (Failure Mode Effective Critical Analysis*)


* Developed by Equity Services & Solutions Co., Ltd

Failure modes and effects analysis (FMEA)

FMEA is an analytical method to study the cause and effects likely to affect the equipment in an operating system in order to:

- assess the effects of each failure mode on the equipment in a system and on the various functions of the system
- identify the failure modes significantly affecting the reliability, availability, maintainability or safety of the system.

The main steps in the performance of an FMEA are illustrated




The FMEA methodology provides:

- Assurance that all conceivable failure modes and their effects on the system operation have been taken into account in the design or operation phase
- Identification of single failures, particularly where safety systems are generally designed to meet the single failure criterion
- An inventory of failure modes according to the extent of their effects on the system functions
- Identification of secondary failures and required redundancy
- Design of detection systems (for example, alarms, periodic tests) for the failure mode; the adequacy of these can be appraised
- Development of the appropriate maintenance procedure corresponding to each failure mode.

3. Work scope

The study cover the gas turbine driving export gas compressor for one unit only (three units are identical), and partly of fuel gas system (full scale RCM study of fuel gas system is separated) as per sketch.



4. Details

4.1 This RCM study is based on:

- 4.1.1 MTTR (Mean Time To Repair) is not including the “lead time” of the work preparation or spare part.
- 4.1.2 Repair or replace process is based on spare module, assembly available e.g. starter, electric motor, gas producer module, etc.
- 4.1.3 On condition maintenance covers “on-line” and “off-line” and “occasion”
 - On-line maintenance consists of all operating/process parameters, vibration analysis, oil analysis (RBOT), thermo-graphic, emission analysis, strain measurement, UTM, Pulse eddy current, and including visual external inspection.
 - Off-line maintenance consists of all internal inspection, pressure test, geometric measurement, NDT, function test / calibration, Etc which requires to shutdown the system.
 - Occasion maintenance is maintenance activity that schedule to be aligned with scheduled off-line maintenance.
- 4.1.4 Unplanned shows in RCM study as breakdown maintenance
- 4.1.5 Scheduled maintenance (either overhaul or replacement) interval is pre-fixed in master plan.
 The firm schedule maintenance will be based on the condition assessment which should be implemented 3-6 months ahead from the pre-fixed schedule using the projection/prediction technique.

4.1.6 Operating context:

Turbo-compressor function (TEK-3200/3300/3400)

All three compressors are installed at PP to deliver gas from separation process to 33,3 % x 3 duty.

Custodian transfer is made at PP via flow-computer.

Operating condition

First stage Inlet parameter
 Pressure, Barg : 23,1 (mean) max 24, min 23,0
 Inlet temp, C : 24,4 (mean), max 25,6
 MW 26,05 kg/kmol
 Compressibility: 0,92 (inlet)
 See gas compositions attached
 Operating speed, rpm: 5900-6100 range



First stage discharge

Pressure, barg: 56,3

Temp, C: 99,9

Second stage Inlet parameter

Pressure, Barg: 54, 1 (mean) max, min

Inlet temp, C: 50,8 (mean), max

MW: 26,05 kg/kmol

Compressibility: 0,865(inlet)

See gas compositions attached

Operating speed, rpm: 5900-6100 range

Second stage discharge

Pressure, barg: 108,2 (mean), 112 (max)

Temp, C: 119,8

Total Reliability and availability

Reliability: 99 %

Availability: 95 %

Each of gas compression train

Availability: 98,5 %

Reliability: unable to pinpoint due to insufficient information.

Delivery agreement, penalty

Guarantee point at delivery at 630 MMscfd (max)

Each compressor train comprise of:

LM-2500 gas turbine

PG-25 power turbine

NP: 2BCL-608, compressor, internal combine stage (1+2),

Lubrication system

GG uses synthetic oil: Mobil and TOTAL, VG-32

PG & comp used mineral oil: TOTAL VG-32

Seal system

Dry gas seal: John crane T28AT

Tandem arrangement

Buffer stage 1: Process gas

Buffer stage 2: Instrument air

LM-2500

Requires fuel gas: 7780kg/h (max) at 31 barg

NP-2BCL-608

Each train, inlet gas before reaching gas compressor train has to be knock-out inlet liquid at suction scrubber.

After 1st stage compression: 99,9 deg C will be cooled by 1st air/gas cooler (A3230) to 52,4 deg C.

At 2nd stage, inlet stream will be combined with side stream at 54,1 Barg at 50,8 deg C. prior reaching 2nd comp unit, gas will be scrubbed by 2nd KO (D-3240)

Final outlet from 2nd compressor: 108 barg at 119 deg C will be cooled down via air / gas cooler (A3260) at 107,2 barg at 50 deg C.

4.1.7 Primary and secondary functions

As described, RCM is based on FMEA technique. Primary & secondary functions are determined from the above operating context as:

1	To deliver gas at 210 MMscfd at the operating condition
2	To meet availability 98,5%
3	To meet reliability 99%
4	To maintain lube oil/liquid containment
5	To maintain process gas containment
6	To limit discharge temp < 120 deg C at inlet 26 (1st) , 54 (2 nd st)
7	To maintain structural integrity
8	To maintain emergency response-life saving-asset integrity
9	To maintain the ignition integrity

4.1.8 Cost critical analysis is based on:

Operational capability		Rate, Baht/hour	
Production capacity, MMscf/hour	8,75	Specialist	3000
Loss, of full capacity/hour	100%	Elect	320
Deferment, from loss of full capacity/hour	2%	Helper	170
Sale price, Baht/MMscfh	238 095,24	Instr	320
		Mech	390
		Prod	320
		Tech-Elec	450
		Tech-Instr	450
		Tech-Mech	630
		Welder	210

In addition, the total production loss of 28,013,400 million Baht is base on the penalty if no total-sale after 24 hours with the loss of sale opportunity of 5% interest

Parts and material cost is specified in each of failure mode individually.

4.1.9 Risk Assessment

Risk assessment is quantified using the specific Risk Matrix and failure consequences which is developed to

				Risk Assessment Matrix			
				Production losses			
				25%	50%	75%	100%
				A	B	C	D
Evident but no effects on HSE, environment of operation	Mild	72 h	1				
Evident degraded operation capacity, No effects on HSE		12 h	2				
Hidden degraded operation/non-operation capability, No effect on HSE		asap	3				
Evident safety and/or environment hazard	Lost of life	HSE	4				
Hidden safety and/or environment hazard							

Sample Coding 1B0.5

1 No effect to HSE
B Cause production lost 50%
0,5 Probability occur 1 in every 2 years

4A0.25

4 Potential to lost of life or injure
A Cause production lost 25%
0,25 Probability occur 1 in every 4 years

4.1.10 Maintenance strategy

Maintenance strategy decision is based on the lowest quantified cost amongst tasks categories which the methodology is made differently as:

- "On Condition Maintenance (OCM)" has to be corporate with "Incipient failure" failure mode only.
 The cost of OCM is based on person(s) who carry out the On Condition Monitoring and assessment only.
 The subsequent "scheduled maintenance" cost is not considered on this maintenance task category.
 It is recommended that NON RECURRING MAINTENANCE & BUDGET should be reserved.
- "Scheduled Overhaul (SO)" will be carried out when it gives the lowest cost without effects to HSE
 The cost of SO is base on the total OCM cost (assuming equivalent to the total man-hour requirement for SO) plus spare parts divided by MTBF plus the cost of Loss & Deferment
- "Schedule Replacement (SR)" will be carried out when it gives the lowest cost without effects to HSE.
 The cost of SR is base on the total OCM cost (assuming equivalent to the total man-hour requirement for SR) plus equipment cost divided by MTBF plus the cost of Loss & Deferment divided by 3
- "Failure Finding (FF)" shall not corporate with "Incipient failure mode"
 The cost of FF is based on person(s) who carry out the FUNCTION TEST only.
 The subsequent "scheduled maintenance" cost is not considered on this maintenance task category
 It is recommended that NON RECURRING MAINTENANCE & BUDGET should be reserved.
- "Corrective Maintenance (CM)" will be carried out when it gives the lowest cost without effects to HSE
 The cost of CM is based on SO cost and further biased with the rejection value of the failure probability.
- "Redesign (RD)" will be commenced when all above are not applicable
 The cost of RD is based on the equipment cost divided by the useful life multiplied by 3

Component corrosion can be applied with this RCM as "Inspection" to be used as "FF"

4.1.11 Failure Characteristic Analysis


Each of failure modes is classified to the 1 of the six failure pattern shown.

Any failure mode that the history could be traced, the maintenance interval can be allocated naturally.

Any failure mode that history could not be traced, the failure pattern and predicted useful life and trouble free life and the potential to failure are model in Weibull curve as the function of:


Weibull probability density/distributions			Probability of failure/rate		
Weibull characteristic			failure rate = at^{b-1}		
			a = scale factor/parameter		
$f(t) = (b/a^b)t^{b-1} \cdot \exp(-(t/a)^b)$			t = time in service		
			b = weibull slope		
b = shape parameter	6				
a = scale parameter	100				
t = start hour	50				

Failure rate $R(T)=1/MTBF$		or probability of failure
or		
$R(T) = at^{b-1}$		
a= scale factor	100	
B = Weibull slop, shape	6	
t = starting time in service	50	



FCA and Propability and Reliability model developed by Manorom C.(ESS Co.,Ltd)

Scale factor = 0,05
 Slope parameter = 3
 Starting time, hours = 750



pattern slope
 A
 B >2
 C 2
 D 1-2
 E 1
 F <1

Useful life, hours = 20000
 Or MTBF as appropriate
 Reject availability 98,00%

Notice. Time scale shall be aligned the "useful life /MTBF" by changing "scale factor" or "starting time"

Interval time should be half life of the reject availability or

800 hours FFI

Figure 1




Figure 1: Six Patterns of Failure

4.1.12 Function and failure mode

Primary/secondary function	
To deliver gas at 210 MMscfd at the operating condition	
Function failure	Failure mode
Gas compressor low performance	Fouling develop at compressor rotor
GG bearing failure due to lubrication degradation	Contaminates in synthetic oil degradation or oxidation.
GG blades fails from foreign object	High vibration due foreign objects to GG from corrosion on vane mist separator, air intake and exhaust ducts
GG low performance from	GG compressor blade fouling
GG unable to operated at desire speed/power	Inlet filter blockage
	TE3200 - High ambient temp, leads to low mass rate
	Fuel gas blockage (offskid)
	FV44220 Control VV, fails close due to controller malfunction
	XV42215 S/d/ VV, fails to stuck open or controller malfunction
	XV42225 fails to function, Loss of fuel gas supply from FV42220,
	TE3200 - Strainer (inlet fuel gas to GG) blockage
	XV42211 malfunction due to loss of instrument air
	LSHH42211 not activate or stuck
	SDV42200 malfunction
	PSV42210 passing
	T5 malfunction or spread due to thermocouples deteriorated
	XV42211 malfunction
	TE3200 - VSV control out of tolerances
	TE3200 - Corrosion cracks on compressor blades or blade coating damaged.
	PDSH42171 malfunction
	ARV42162 clogged up
	PSV42160 passing
	PSV42110 passing
	T42130 (oil/air separator) damaged or clogged up
	PDSL42713 & 15 malfunction
GG unable to start on demand due to starting system failed	TS3200 Gas starter failure
	TE3200 - Starting gas turbine regulating valve system malfunction



Function failure	Failure mode
Insufficient cooling and lubricating GG, PT and compressor bearings.	A42145 & A 42820 - Cooling fan bearing failure.
Insufficient hydraulic oil supply to system	A42145 & A42820 - Transmission belt or pulleys failure. P42160 hydraulic pump failure
Insufficient lube oil to cool and lubricate GG, PT and compressor bearings.	A42145 & A42820 - Cooling fan failure.
Insufficient lube oil to cooling and lubricating compressor and power turbine bearings.	P42850 Filter blockage on discharge of cool down pump PDI42855 incorrect reading at low side TSH42823 malfunction
Insufficient lube oil to lubricate and cool GG, PT and compressor bearings.	M42820, 25 cooler fan motor bearing failure
Insufficient lube oil to lubricate and cool GG bearings.	TE3200 - P42110 synthetic oil pump failure TE3200 - P42140-43 Scavenge pumps failure PSV42246 passing TCV42147 malfunction
Insufficient lube oil supply to cool and lubricate compressor bearings	A42145 & A42820 oil cooler fouling M 42820, M 42825 bearing failure PCV42840 malfunction TV42821 malfunction M42850 bearing failure P42850 bearing failure M42805 bearing failure
Insufficient lube oil supply to cool and lubricate compressor bearings.	PCV42813 malfunction
Poor GG compression performance due to insufficient off-line cleaning on compressor blades	P42610, water wash pump failure M42610 bearing failure, water wash pump T42605 & T42600 tanks corroded or deposit in tanks. Deposits on H42605 heater or heater poor performance
PT or compressor bearing failure due to lubrication degradation	Contaminates in lube oil, mineral oil degradation or oxidation.
Unable to operate compressor on demand	XV3221 malfunction
Unable to operate compressor on demand due to high temp lube oil.	A42820 – Lube oil cooler fouling.
Unable to produce at the optimum point	FV3220 (1st stage anti-surge valve) malfunction
Unable to run compressor continuously due to both lube oil pumps not functioned.	PSL42812 not activated



Function failure	Failure mode
Unable to run compressor smoothly due to spurious trip	LSLL3242 not activated PALL3223 malfunction (1st suction) TAHH3220 malfunction (1st suction) PAHH3226 & PALL3226 malfunction (1st discharge) TAHH3223 malfunction (1st discharge) PALL3253 malfunction (2nd suction) PALL3254 & PAHH3254 malfunction (2nd discharge) TAHH3253 malfunction (2nd discharge) PAHH3259 malfunction (2nd discharge) PDAHH3229 malfunction (PD discharge both stage) PT42842 - PSL malfunction PSH42851 not activated P42850 - F42855 filter blockage P42805 - F42830 & F42835 filter blockage PDSH 42831 not activated TE3200-M42500(AC) bearing failure TE3200-M42502 (DC) bearing failure. TE3200-FDP42500 stuck closed TSHH42502 malfunction TE3200-FSL42500 malfunction PDSHH42501 malfunction PDSL42508 malfunction TE3200-FDP42503 stuck closed SDV3214 malfunction LSL42801 malfunction
Unable to seal gas in the compressor effectively.	Igniter failure
Unable to start compressor due to not permissive to start lube oil pump	Bearing damaged or worn out from aging
Unable to start GG on demand	Rotor dynamics problems: Shaft cracks, shaft bent, rubbing, impeller damaged, etc.
Compressor stop from High thrust / journal bearing temp & vibration	Couplings failure, Misalignment Blockage in compressor drain piping.

Primary/secondary function	
To limit discharge temp < 120 deg C at inlet 26 barg (1stage) , 54 barg (2nd stage)	
Function failure	Failure mode
Insufficient to cooling stage discharge gas.	A3230 - Heat exchanger fouling or paraffin formation inside tube wall.
	A3230 - Cooling fan blade damaged.
	A3230 - Cooling fan bearing failure.
	A3260 - Heat exchanger fouling or paraffin formation inside tube wall.
	A3260 - Cooling fan blade damaged.
	A3260 - Cooling fan bearing failure.
Insufficient to cooling 1st stage discharge gas.	A3230 - M3230A/B/C/D motor bearing failure
	A3230 - Transmission belt failure
Insufficient to cooling 2nd stage discharge gas.	A3260 - M3260A/B/C/D motor bearing failure
	A3260 - Transmission belt failure
	TAHH3220 malfunction (1st suction)
	PAHH3226 & PALL3226 malfunction (1st discharge)
	TAHH3223 malfunction (1st discharge)
	PALL3253 malfunction (2nd suction)
	PALL3254 & PAHH3254 malfunction (2nd discharge)
	TAHH3253 malfunction (2nd discharge)
	PAHH3259 malfunction (2nd discharge)
	PDAHH3229 malfunction (PD discharge both stg)

Function failure	Failure mode
Unable to run compressor smoothly due to spurious trip	TAHH3220 malfunction (1st suction)
	PAHH3226 & PALL3226 malfunction (1st discharge)
	TAHH3223 malfunction (1st discharge)
	PALL3253 malfunction (2nd suction)
	PALL3254 & PAHH3254 malfunction (2nd discharge)
	TAHH3253 malfunction (2nd discharge)
	PAHH3259 malfunction (2nd discharge)
	PDAH3229 malfunction (PD discharge both stg)
<u>Primary/secondary function</u>	
To maintain emergency response-life saving-asset integrity	
Function failure	Failure mode
Unable to stop compressor safely, compressor reverse flow & reverse direction	EI3222, EI3252 (discharge check valve) and station valve stuck opened
Unable to depressurize process gas from the unit	BDV3251 malfunction
<u>Primary/secondary function</u>	
To maintain lube oil/ Liquid containment	
Function failure	Failure mode
Unable to maintain synthetic oil in GG package	T42100 Synthetic oil tank corrosion or deposits in tank
Unable to maintain lube oil in compressor package	Lube oil leakage due to T 42800 outside corrosion
	T42800 Lube oil leakage due to internal corrosion or deposit in tank.
Unable to seal lube oil in cool-down pump	P42850 mech-seal leakage

<u>Primary/secondary function</u>	
To maintain process gas containment	
Function failure	Failure mode
GG unable to operated at desire speed/power	D42210 internal / outside corrosion
Unable to contain gas in the compressor effectively.	PSH42725 malfunction
Unable to operate compressor safely	D3210, D3240 - Internal Corrosion.
Unable to run compressor safely.	D3210, D3240 - External Corrosion.
	A3230, A3260 Internal / External Corrosion
Unable to seal gas in the compressor effectively.	Blockage in primary or secondary DGS vent lines
	DGS failure due to deterioration buffer gas
	Buffer fuel gas supply blockage due to strainer or check valve plugged.
	PDCV42710 malfunction
	PCV42725 malfunction
	No instrument air supply to DGS due to orifice plate plugged
	PDT42710 malfunction
	PDSL42710 malfunction
<u>Primary/secondary function</u>	
To maintain structural integrity	
Function failure	Failure mode
Oil cooling fan blade damage and fly away or possible tube damage	VSH42820, VSH42825 Vibration switch not activated

<u>Primary/secondary function</u>	
To maintain the ignition integrity	
Function failure	Failure mode
Fire inside the package enclosure	Unable to fire protection in enclosure due to Faults from fire detectors or no fire suppression medium
Insufficient to fire fighting due to damper not fully closed.	Damper stuck opened.
Unable to alert when hot gas leakage in enclosure.	TSHH 42502 malfunction
Unable to control flame explosion.	Flame arrestor malfunction or internal corrosion
Unable to control flame explosion	Gas detector malfunction
<u>Primary/secondary function</u>	
To meet availability 98,5%	
Function failure	Failure mode
Short components life from high temperature expose	High temp alarm in enclosure due to ventilation fails
Turbine blade damage from fatigue life	GG blade damage from fatigue or hot path or corrosion
Turbine blade damage from fatigue life	PT blade fatigue damage

<u>Primary/secondary function</u>	
To meet reliability 99%	
Function failure	Failure mode
Unable to indicate correct machine condition	Vibration displacement probes failure due to deterioration
	Vibration accelerometer failure due to deterioration
	Vibration seismic probe failure due to deterioration
Unable to indicate correct speed on GG or PT	Speed probes (eddy current) failure due to deterioration
Unable to indicate correct speed or key phasor for compressor	Vibration displacement probes failure due to deterioration
Unable to monitor or verify actual equipment condition.	PT 42215, 16, 17, 18 malfunction
	PI42230 malfunction
	TSL42211 malfunction
	PSL42173 malfunction
	PI42172 malfunction
	PDI42170 malfunction
	All gages (PI, PDI, TI, LG, FG) malfunction
Unable to protect compressor bearings failure when low lube oil pressure.	PSLL42843 malfunction
Unable to run compressor smoothly due to condition monitoring system faults	Bently Nevada system malfunction
Unable to run compressor smoothly due to spurious trip	LV3214 malfunction
	LAHH3211 malfunction
	SDV3210 malfunction
	PSV3230, PSV3258 passing
	LV3244 malfunction
	LAHH3241 malfunction



บริษัท อีควิตี้ เซอร์วิสเชส แอนด์ โซลูชั่นส์ จำกัด
 801/138 หมู่8 ถนนพหลโยธิน
 ต.คูคต อ.ลำลูกกา จ.ปทุมธานี 12130.
 โทร. 0 2992 5040 โทรสาร 0 2992 5041
 โทร. 0 2998 7308 โทรสาร 0 2998 7309
 อีเมล : esspower@esspower.com
manorom@bteng.com

Equity Services & Solutions Co., Ltd
 801/138 Moo 8 Phaholyothin Rd.,
 Ku-Kod, Lamluka, Prathumthanee12130
 Tel : 0 2992 5040, Fax : 0 2992 5041
 Tel : 0 2998 7308, Fax : 0 2998 7309
 Email : esspower@esspower.com
manorom@bteng.com

Function failure	Failure mode
Unable to run compressor smoothly due to spurious trip	SDV3242 malfunction
	SDV3241 malfunction
	FV3250 (2nd stg anti-surge valve) malfunction
	FE3250 malfunction-Blockage or corrosion
	PSV3210 passing
	SDV3211 malfunction
	FE3220 malfunction
	FT3200 malfunction-stuck sticky
	TE3200-Fuel gas strainer blockage
Unable to run GG smoothly due to turbine control system faults	TCP system malfunction
Unable to stop lube oil emergency pump when oil pressure reach 1.8 bar	PSH42844 not activated

4.1.13 Failure mode and local effects and consequences

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
Bearing damaged or worn out from aging	Compressor trip	Possible shaft journal damaged.		C-Evident degraded operation capacity, No effects on HSE	2	D
Rotor dynamics problems: Shaft cracks, shaft bent, rubbing, impeller damaged, etc.	Catastrophic failure on compressor	Compressor trip from high vibration		C-Evident degraded operation capacity, No effects on HSE	2	D
Couplings failure, Misalignment	Compressor trip from high vibration.	Leads to bearing damages	Possible trip from over speed	C-Evident degraded operation capacity, No effects on HSE	2	D
Unable to fire protection in enclosure due to Faults from fire detectors or no fire suppression medium	GG trip.	Properties loss	Possible people endanger	A-Hidden safety and/or environment hazard	4	D
Fouling develop at compressor rotor	High discharge temp	Low throughput		C-Evident degraded operation capacity, No effects on HSE	2	D
Contaminates in synthetic oil degradation or oxidation.	Cause GG bearings damaged.			C-Evident degraded operation capacity, No effects on HSE	2	D
High vibration due foreign objects to GG from corrosion on vane mist separator, air intake and exhaust ducts	Damage compressor blades and high vibration may lead to GG trip.			C-Evident degraded operation capacity, No effects on HSE	2	D
GG compressor blade fouling	High T2	Low P3		C-Evident degraded operation capacity, No effects on HSE	2	D
Inlet filter blockage	Low mass rate, leads to high heat rate	High diff pressure across filter > 250 mmWG	High Temp pdc, low PCD	C-Evident degraded operation capacity, No effects on HSE	2	B
TE3200 - High ambient temp, leads to low mass rate	Low mass rate, leads to high heat rate	Possible T5 topping		C-Evident degraded operation capacity, No effects on HSE	2	A
Fuel gas blockage(offskid)	Fuel gas filter trip by LL trip. Alarm 29 Barg			C-Evident degraded operation capacity, No effects on HSE	2	B
FV44220 Control VV, fails close due to controller malfunction	Fuel gas fluctuated and may leads to GG trip.			C-Evident degraded operation capacity, No effects on HSE	2	B

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
XV42215 S/d/ VV, fails to stuck open or controller malfunction	Unable to start from isolation test function during ramp start up	Possible explosion due to incomplete purge		A-Hidden safety and/or environment hazard	4	D
XV42225 fails to function, Loss of fuel gas supply from FV42220,	Loss of fuel gas, leads to GG trip			C-Evident degraded operation capacity, No effects on HSE	2	C
TE3200 - Strainer (inlet fuel gas to GG) blockage	Loss of fuel gas, leads to GG trip			C-Evident degraded operation capacity, No effects on HSE	2	B
XV42211 malfunction due to loss of instrument air	Loss fuel gas to GG leads to low power GG	LP flare will receive more flow	Possible low fuel gas pressure	C-Evident degraded operation capacity, No effects on HSE	2	A
LSHH42211 not activate or stuck	Liquid fuel may carry over to GG			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
SDV42200 malfunction	If stuck closed, it is unable to start GG	No fuel gas into system		C-Evident degraded operation capacity, No effects on HSE	2	C
D42210 outside corrosion	Lead to fuel gas leakage or explosion			B-Evident safety and/or environment hazard	4	D
D42210 internal corrosion	Lead to fuel gas leakage			B-Evident safety and/or environment hazard	4	D
PSV42210 passing	Fuel gas leak to flare. But operators can close manual valve on down stream line.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
T5 malfunction or spread due to thermocouples deteriorated	Alarm on T5	It requires to replace thermocouples ASAP.		C-Evident degraded operation capacity, No effects on HSE	2	A
XV42211 malfunction	If stuck closed, possible liquid high level trip GG	If leakage during GG running, GG may be uncontrollable or performance drop.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
TE3200 - VSV control out of tolerances	To reduce GG speed cause lower production.	Compressor surge or more stress on 1st stage compressor blades may be presented.		C-Evident degraded operation capacity, No effects on HSE	2	A
TE3200 - Corrosion cracks on compressor blades or blade coating damaged.	Possibly broken compressor blades may cause catastrophic failure on GG.			C-Evident degraded operation capacity, No effects on HSE	2	D
PDSH42171 malfunction	No alert to operation when hydraulic oil filter blockage.	Reading on PI 42172 can be verified.	Filter blockage cause hydraulic oil pressure drop until PSL 42173 alarm.	E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
ARV42162 clogged up	Air may be blockage in hydraulic oil supply.	It may cause fuel control system malfunction.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PSV42160 passing	Hydraulic oil pressure dropped and fluctuated.	Fuel control system may be uncontrollable.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PSV42110 passing	Lube oil pressure drop may lead to GG low lube oil pressure trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
T42130 (oil/air separator) damaged or clogged up	Air may plug in lube oil passage.	Insufficient lube oil to cooling and lubricating GG bearings lead to GG trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PDSL42713 & 15 malfunction	It may cause permissive to start fails, lube oil pump.	Can not start compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TS3200 Gas starter failure	No throughput due to unable to operate			C-Evident degraded operation capacity, No effects on HSE	2	D
TE3200 - Starting gas turbine regulating valve system malfunction	Delay on start-up due to fix the regulator.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
A42145 & A 42820 - Cooling fan bearing failure.	Vibration switches may be activated to trip motor.	High temp in lube oil tank.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A42145 & A42820 - Transmission belt or pulleys failure.	It may cause belt slip and pulleys worn out.	Vibration switches may be activated to trip motor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
P42160 hydraulic pump failure	Fuel control valve not function and cause GG trip			C-Evident degraded operation capacity, No effects on HSE	2	D
A42145 & A42820 - Cooling fan failure.	Vibration switches may be activated alarm and trip motor.	High temp in lube oil tank.	Broken blade may hit cooler tubing, and possible it may cause oil leakage.	B-Evident safety and/or environment hazard	4	A
P42850 Filter blockage on discharge of cool down pump	Insufficient cooling PT may cause bearing cooking.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
PDI42855 incorrect reading at low side	No indication for filter blockage of cool down pump.	If actual filter blocked, insufficient cooling PT may occur.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
TSH42823 malfunction	No alert sent to operation when high lube oil temp. Consequently, more wear and tear on bearings may be presented.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No



<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
M42820, 25 cooler fan motor bearing failure	High temp lube oil may cause insufficient cooling and lubricating GG bearings, lead to high deterioration of bearings.	May lead to belt damaged, high wear & tear of pulley.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
A3230 - M3230A/B/C/D motor bearing failure	Motor may trip from overload current.	High temp on 1st discharge gas.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A3230 - Transmission belt failure	Motor may trip from overload current or underload current.	High temp on 1st discharge gas.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A3260 - M3260A/B/C/D motor bearing failure	Motor may trip from over current.	Noisy to surroundings.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A3260 - Transmission belt failure	Motor may trip from overload current or underload current.	Noisy to surroundings.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A3230 - Heat exchanger fouling or paraffin formation inside tube wall.	High temp on 2nd stg suction gas.	Compressor performance drop.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A3230 - Cooling fan blade damaged.	High temp on 2nd stg suction gas.	High vibration transmit to structure and equipment, it may cause fin tubes damaged.	People endanger	B-Evident safety and/or environment hazard	4	A
A3230 - Cooling fan bearing failure.	High vibration transmits to structure and equipment.	Possible motor tripped due to overload current.	High temp on 2nd stg suction gas.	C-Evident degraded operation capacity, No effects on HSE	2	A
A3260 - Heat exchanger fouling or paraffin formation inside tube wall.	High temp on discharge gas to glycol contactor.	Compressor performance drop.		C-Evident degraded operation capacity, No effects on HSE	2	A
A3260 - Cooling fan blade damaged.	High temp on discharge gas to glycol contactor.	High vibration transmits to structure and equipment, it may cause fin tubes damaged.	People endanger	B-Evident safety and/or environment hazard	4	B
A3260 - Cooling fan bearing failure.	High vibration transmits to structure and equipment.	Possible motor tripped due to overload current.	High temp on 2nd stg suction gas.	C-Evident degraded operation capacity, No effects on HSE	2	A
Damper stuck opened.	Possible loss of properties	Possible people endanger		A-Hidden safety and/or environment hazard	4	D
TE3200 - P42110 synthetic oil pump failure	Low lube oil pressure and lead to GG trip			C-Evident degraded operation capacity, No effects on HSE	2	D
TE3200 - P42140-43 Scavenge pumps failure	Oil sump temp increased, may lead to GG trip.			C-Evident degraded operation capacity, No effects on HSE	2	B



<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
PSV42246 passing	Too much hot oil bypass to synthetic oil tank	Scavenge pressure drop may lead to alarm.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
TCV42147 malfunction	High temp lube oil may cause insufficient cooling and lubricating GG bearings, may lead to GG trip.	High temp in lube oil tank.	Can isolate TCV and use bypass valve to manual control after cooled temp.	E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
A42145 & A42820 oil cooler fouling	High temp synthetic oil may cause insufficient cooling and lubricating GG bearings, lead to high deterioration of bearings.	High temp in lube oil tank.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
M 42820, M 42825 bearing failure	Motor may trip from over current.	Standby fan motor need to start immediately		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
PCV42840 malfunction	Lube oil header pressure may be fluctuated or hunting. It may cause lube oil pressure trip.			C-Evident degraded operation capacity, No effects on HSE	2	A
TV42821 malfunction	High lube oil temp. cause insufficient cooling and lubricating bearings. But it can do manual control when TV fault.	In case operators not action when TV faults, it may cause high temp lube oil trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
M42850 bearing failure	Insufficient lube oil to cool-down PT during shutdown.	Insufficient cooling PT may cause rotor bent.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	C
P42850 bearing failure	Insufficient lube oil to cool-down PT during shutdown.	Insufficient cooling PT may cause rotor bent.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	C
M42805 bearing failure	Motor may trip from overload current.	Lube oil pressure drop and standby pump will start up automatically		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
PCV42813 malfunction	Lube oil back pressure may be fluctuated or hunting. If high back pressure, it can relief pressure on PSV.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	C
VSH42820, VSH42825 Vibration switch not activated	No signal to stop motor may cause high vibration to structure and consequently damage equipment.	Lube oil temp may be high and lead to GG trip.	Possible oil spill	A-Hidden safety and/or environment hazard	4	A
P42610, water wash pump failure	Delay on offline water wash , to fix wash pump			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
M42610 bearing failure, water wash pump	Delay to offline water wash , to fix wash pump			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
T42605 & T42600 tanks corroded or deposit in tanks.	Water wash leak to the external			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Deposits on H42605 heater or heater poor performance	Rinsing water heat up insufficiently	insufficient cleaning efficiency		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Contaminates in lube oil, mineral oil degradation or oxidation.	Cause PT and compressor bearings damaged.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	C
High temp alarm in enclosure due to ventilation fails	System will alarm	High temp enclosure trip		D-Evident but no effects on HSE, environment of operation	1	A
GG blade damage from fatigue or hot path or corrosion	GG possible total damage	Possible leads to fluid containment fails		B-Evident safety and/or environment hazard	4	D
PT blade fatigue damage	PT possible total damage	Possible leads to fluid containment fails		B-Evident safety and/or environment hazard	4	D
PSH42725 malfunction	If on high to alarm, it may be noise to operator.	If on low side, no action may cause loss of a lot of instrument air.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Flame arrestor malfunction or internal corrosion	In case of fuel gas leakage, flame may explode to atm.			A-Hidden safety and/or environment hazard	4	A
Gas detector malfunction	If sensor faults, it cause erratic trip on the compressor.	No safeguarding when fuel gas leakage from DGS failure.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
BDV3251 malfunction	If stuck closed when unit need to depressurize, it need to open bypass valve to flare immediately	If leakage during operation, it cause loss of process gas to flare. But operators can close manual valve on down stream line.		A-Hidden safety and/or environment hazard	4	A
Vibration displacement probes failure due to deterioration	Sensitivity changes cause incorrect readings and dynamic response.	Probe tip may be broken and cause erratic fault or trip on the compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Vibration accelerometer failure due to deterioration	Sensitivity changes cause incorrect readings and dynamic response.	Spike vibration from failed probes may cause GG trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
Vibration seismic probe failure due to deterioration	Sensitivity changes cause incorrect readings and dynamic response.	Spike vibration from failed probes may cause GG trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Speed probes (eddy current) failure due to deterioration	Sensitivity changes cause incorrect readings and dynamic response.	Another spare speed probe can be used.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Vibration displacement probe failure due to deterioration	Sensitivity changes cause incorrect readings and dynamic response.	Less ability to detect machine condition.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
Lube oil leakage due to T 42800 outside corrosion	Lube oil spill to external may cause fire.			B-Evident safety and/or environment hazard	4	A
T42800 Lube oil leakage due to internal corrosion or deposit in tank.	Lube oil spill to external may cause fire.	Deposits in lube oil system often clog up the filter.		B-Evident safety and/or environment hazard	4	A
T42100 Synthetic oil tank corrosion or deposits in tank	Oil leakage to outside, often clog up in lube oil filters			B-Evident safety and/or environment hazard	4	D
PT 42215, 16, 17, 18 malfunction	2 of 3 voting shall have no effect on GG.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PI42230 malfunction	No instrument to verify fuel flow and combustion performance			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
TSL42211 malfunction	No alert when fuel gas temp over 45 deg C.	Reading on TI 42210 can be verified.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
PSL42173 malfunction	No alert to operation when hydraulic oil supply faults.	Reading on PI 42172 can be verified.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PI42172 malfunction	No reading on hydraulic oil pressure			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PDI42170 malfunction	No reading on hydraulic filter diff pressure.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
All gages (PI, PDI, TI, LG, FG) malfunction	No corrected readings may cause misinformation for problem			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
XV3221 malfunction	Valve stuck closed during startup cause unable to balance compressor pressure and permissive to start compressor fails.	If valve leakage during operation, it will cause compressor performance drop		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
A42820 - Lube oil cooler fouling.	High lube oil temp. May cause insufficient cooling and lubricating bearings.			C-Evident degraded operation capacity, No effects on HSE	2	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
D3210, D3240 - Internal Corrosion.	Combustible gas may leak to external and cause fire.			B-Evident safety and/or environment hazard	4	D
FV3220 (1st stg anti-surge valve) malfunction	It cause process surging and may be compressor trip from vibration.	Process down stream fluctuated		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
PSLL42843 malfunction	If not activate when low lube oil pressure, it may cause compressor bearings damaged.	No lube oil supply to cooling PT during shutdown. It may PT rotor bent.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PSL42812 not activated	When lube oil pressure lower than 6.5 bar, automatic start standby pump is not functioned.	Unfortunately, if main pump failure and manual start standby pump not in time; compressor may trip from low lube oil pressure.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
D3210, D3240 - External Corrosion.	Combustible gas may leak to external and cause fire.			B-Evident safety and/or environment hazard	4	D
A3230, A3260 Internal / External Corrosion	Combustible gas may leak to external and cause fire.			B-Evident safety and/or environment hazard	4	D
Bently Nevada system malfunction	Compressor trip or can not start up.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
LSLL3242 not activated	No signal to close SDV3214.	LV3244 can be closed automatically or operators can close a manual valve as well.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
LV3214 malfunction	If stuck closed, operators need to open manual valve to drain header.	If stuck open, it can isolate the valve for maintenance or replace online.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
LAHH3211 malfunction	If not activate when high liquid, compressor trip from high vibration	If stuck on high level, it cause erratic fault or not permissive to start compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
SDV3210 malfunction	If stuck closed, it cause unable to start compressor.	If stuck partially opened, it needs to close upstream ball valve.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
PSV3230, PSV3258 passing	Loss process gas and compressor performance drop. But operator can close manual valve on down stream line.	Noisy to surroundings.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
PALL3223 malfunction (1st suction)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
TAHH3220 malfunction (1st suction)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PAHH3226 & PALL3226 malfunction (1st discharge)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
TAHH3223 malfunction (1st discharge)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PALL3253 malfunction (2nd suction)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PALL3254 & PAHH3254 malfunction (2nd discharge)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
TAHH3253 malfunction (2nd discharge)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PAHH3259 malfunction (2nd discharge)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
PDAHH3229 malfunction (PD discharge both stg)	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
LV3244 malfunction	If stuck closed, operators need to open manual valve to drain header.	If stuck open, it can isolate the valve for maintenance or replace online.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
LAHH3241 malfunction	If not activate when high liquid, compressor trip from high vibration	If stuck on high level, it may cause erratic alarm or trip on the compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
SDV3242 malfunction	If stuck closed, high liquid level (LAHH3241) may cause compressor trip.	If stuck open, LV3244 (automatic closed drain to 2nd stg separator) and closed drain header lines can be closed by manual valves.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D



<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
SDV3241 malfunction	If stuck closed, it need fuel gas from well head supplying to GG.	If stuck partially opened when ESD active, gas can pass to blow down valve.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
FV3250 (2nd stg anti-surge valve) malfunction	It cause process surging and may be compressor trip from vibration.	Process down stream fluctuated		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
FE3250 malfunction-Blockage or corrosion	If erosion or corrosion caused oversize diameter, incorrect readings may cause anti-surge valve function improperly.	If blockage, it can not to run compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
PSV3210 passing	Loss of process gas to flare. But it can close down stream line by manual valve (HV3210)			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
SDV3211 malfunction	Not open, can override signal to open SDV3210			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
FE3220 malfunction	If erosion and corrosion caused oversize diameter, incorrect readings may cause anti-surge valve function improperly.	If blockage, it can not to run compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	B
FT3200 malfunction-stuck sticky	No effect to GG operation, only cannot do performance calculation.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TE3200-Fuel gas strainer blockage	Insufficient fuel gas supplies to GG and PSL 42211 alarm on low pressure.	Possible GG trip or lower speed.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PT42842 - PSL malfunction	If unit running, when low lube oil pressure PSL not activated to start standby pump, it may cause compressor trip.	If unit shutdown, when main lube oil pump cannot build pressure enough and standby pump not start, it may cause delay to start compressor.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PSH42851 not activated	No status on cool down pump running properly is presented. But operators can verify its status with local PI42850 or PI42844.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
P42850 - F42855 filter blockage	Insufficient lube oil supply to cool down PT rotor during unit shutdown.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
P42805 - F42830 & F42835 filter blockage	Insufficient lube oil supply may cause high bearing temp trip.	However, PDSH42831 activated alarm, operator need to switch over standby filter.		C-Evident degraded operation capacity, No effects on HSE	2	A
PDSH 42831 not activated	No status on lube oil filter blockage is presented.	If not switch over to standby filter in a proper time, insufficient lube oil supply may cause high bearing temp trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TE3200-M42500(AC) bearing failure	Low pressure alarm and activated standby ventilation fan running, in worse case possible high temp in enclosure room trip.	In case motor overload trip, standby fan will start automatically.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TE3200-M42502 (DC) bearing failure.	If loss of AC power, insufficient ventilation for cooling in enclosure room when GG shutdown.	High temp in enclosure room may cause failure on instrumentation.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
TE3200-FDP42500 stuck closed	Low pressure alarm and activated standby ventilation fan running.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
TSHH42502 malfunction	Erratic signal may cause compressor trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TE3200-FSL42500 malfunction	Improper ventilation fan operation can not be presented.	High temp in enclosure room can be presented alternatively.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PDSHH42501 malfunction	If over activated fault, it cause GG erratic trip.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PDSL42508 malfunction	When ventilation fan fault, no signal to start standby vent fan.	High temp in enclosure room may cause GG trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TE3200-FDP42503 stuck closed	High pressure in enclosure room.	High temp in enclosure room may cause GG trip.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
TCP system malfunction	GG trip or can not start up			C-Evident degraded operation capacity, No effects on HSE	2	D
Blockage in primary or secondary DGS vent lines	Insufficient cooling on DGS face, heat up to cause DGS failure.	Compressor trip.		C-Evident degraded operation capacity, No effects on HSE	2	C

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
DGS failure due to deterioration buffer gas	Compressor trip.			C-Evident degraded operation capacity, No effects on HSE	2	D
Buffer fuel gas supply blockage due to strainer or check valve plugged.	PDSL 42710 activated alarm.	Dirt from process gas may pass to DGS and cause primary DGS failure.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	C
PDCV42710 malfunction	Operators have to open bypass valve immediately.	Dirt from process gas may pass to DGS and cause primary DGS failure.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PCV42725 malfunction	Stuck open, PSH44725 activated alarm. Loss instrument air.	Stuck closed, buffer gas may leak to 2nd seal and gas contaminated lube oil.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
No instrument air supply to DGS due to orifice plate plugged	PDSL44713 & 14 activated alarm.	Stuck closed, buffer gas may leak to 2nd seal and gas contaminated lube oil.		C-Evident degraded operation capacity, No effects on HSE	2	A
PDT42710 malfunction	Improper control clean gas to against process gas leak to DGS			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
PDSL42710 malfunction	If not activated when true, it may cause no immediate action to verify the problem.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A
SDV3214 malfunction	If stuck closed, high liquid level (LAHH3211) may cause compressor trip.	If stuck open, LV3214 (automatic closed drain to 2nd stg separator) and closed drain header lines can be closed by manual valves.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
P42850 mech seal leakage	Lube oil spill to atm may cause fire.			B-Evident safety and/or environment hazard	4	A
LSL42801 malfunction	If stuck high and actual low level, it may cause lube oil pump run dry until motor trip.	If stuck low, during compressor startup sequences, main lube oil pump can not start due to impermissible from lube oil level fault.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
Igniter failure	No throughput due to unable to operate			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	D
EI3222, EI3252 (discharge check valve) and station valve stuck opened	Back pressure may cause compressor rotor reversal turning.	Possible DGS damaged.		E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

<u>Failure mode</u>	<u>Local & System effect-1</u>	<u>Local & System effect-2</u>	<u>Local & System effect-3</u>	<u>Consequence and Category</u>	<u>Recovery, class</u>	<u>Severity class</u>
PSH42844 not activated	Not signal to stop cool down pump, it may cause hot pump running if not stop by manual.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	No
TSHH 42502 malfunction	Possibly damage or burn instruments and controls.			E-Hidden degraded operation/non-operation capability, No effect on HSE	3	A

5. Maintainable item and interval and maintenance technique

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
daily	On line	Prod	On condition maint	1) Since it is A/B/C/D arrangement, to monitor and switchover is normal practice. 2) While switchover, replacement filter is a must. 3) However, there are automatic control valves to open a bypass line across the filters when blockage.	Fuel filter skid
daily	On line	Prod	On condition maint	Walk around observe for noise & temp profile from passing	PSV-3210
daily	On line	Prod	On condition maint	Daily, verify that no passing leak of anti surge valve at normal operation	FV-3220
daily	On line	Prod	On condition maint	Daily check& record lube oil temp and pressure.	PSV 42246
monthly	On line	Prod	On condition maint	1) Monthly measure record fuel gas pressure	TE-3200 - Fuel gas strainer
daily	On line	Mech	On condition maint	1) Walk around to observe noise of icing from high gas flow 2) Visual check at valve stem position 3) Recommend to install work instruction at local.	XV-42211
daily	On line	Mech	On condition maint	Monitor & record lube oil pressure (PI42125) and temp (TE42121).	P-42110 PI-42125 TE-42121
daily	On line	Mech	On condition maint	Monitor & record oil sump temp and sump discharge pressure.	P-42140 P-42141 P-42242 P-42103
daily	On line	Mech	On condition maint	Monitor & trending diff. temp between TI 42144 and TI 42145.	A-42145 TI-42144 TI-42145
daily	On line	Mech	On condition maint	Monitor PDI 42170 and PI 42172 in order to verify hydraulic pump problem.	P-42160 PSV-42160 PDI-42170 PI-42172

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
daily	On line	Mech	On condition maint	1) Monitor for trending T5 element profile 2) Occasion planned to replacement	T5 element
daily	On line	Mech	On condition maint	Daily measure record seal buffer gas pressure and flow and vent pipe skin temp	DGS : buffer gas filter system
daily	On line	Mech	Scheduled overhaul	Walk around to observe any abnormal noise, vibration or belt tension.	M-42145 M-42845 A-3230 A-3260
daily	On line	Mech	On condition maint	1) Observe PDI42830 in order to monitor the filter blockage. 2) Change over filter and clean filter when PDSH42831 is alarmed	F-42830 F-42835 PDI-42830 PDSH-42831
daily	On line	Mech	On condition maint	Measure skin temp of gas vent pipe for trending	DGS FV-42710 FV-42711 PSE-42720 PSE-42723
daily	On line	Mech	On condition maint	Daily check & record for trending	PDI-42170
daily	On line	Mech	On condition maint	Daily, verify that no passing leak of anti surge valve at normal operation	FV-3250
daily	On line	Mech	On condition maint	Walk around inspection in order to find any corrosion or insulation damaged.	D-42210
monthly	On line	Mech	On condition maint	1) Vibration analysis and trend analysis. 2) Occasion to replace bearing from trend analysis	M-42820 M-42825
monthly	On line	Mech	On condition maint	1) Measure & record vibration analysis comparing to baseline spectrum. 2) Measure & record motor running current	M-42610
monthly	On line	Mech	On condition maint	Measure & record vibration	A-42145 A-42845
monthly	On line	Mech	On condition maint	1) Vibration analysis for motor of ventilation fan in order to check bearing faults. 2) Planned to replace ventilation fan from trend analysis	TE-3200, Enclosure ventilation fan
monthly	On line	Mech	On condition maint	1) Monitor TI3230 & TI3232 for trending. 2) Vibration analysis	A-3230 TI-3230/TI-3232 All bearings A-3260
monthly	On line	Mech	On condition maint	Vibration analysis and trend analysis.	M-42805 M-42810
monthly	On line	Mech	On condition maint	Monitor & trending diff. temp between	A-42820

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
				TI42812 and TI42820.	TI-42812, TI-42820
monthly	On line	Mech	On condition maint	Vibration analysis and trend analysis.	M-42820 M-42825
monthly	On line	Mech	On condition maint	1) Vibration analysis and trend analysis.	A-42145 A-42845
monthly	On line	Mech	On condition maint	1) Vibration analysis and trend analysis.	M-3230A/B/C/D
monthly	On line	Mech	On condition maint	1) Vibration analysis and trend analysis.	M-3260A/B/C/D
monthly	On line	Mech	On condition maint	1) In case abnormal noise or vibration, further vibration analysis comparing to baseline shall be performed. (If bearing faults founded, switching to use standby fan running and carry out recondition)	M-42500 M-42501
monthly	On line	Mech	On condition maint	Record data for trending	PI-42230
monthly	On line	Mech	On condition maint	Monitor & record lubeoil temp and pressure.	T-42130
monthly	On line	Mech	On condition maint	Walk around to observe any corrosion or insulation material damaged.	D-3210 D-3240
monthly	On line	Mech	On condition maint	Measure vibration and record for trending	M-42502
3 months	Occasion	Mech	On condition maint	1) Inspect and clean the strainer, replace as necessary	TE-3200
3 months	Off line	Mech	On condition maint	Carry out off line water wash per compressor performance monitoring.	TE-3200
6 months	Occasion	Mech	Scheduled overhaul	Visual inspection and measure/adjust belt tension	M-42145 M-42845 A-3230 A-3260
6 months	Occasion	Mech	Scheduled overhaul	Check and adjust belt tension or replace belt if required.	A-42145 A-42845
1 year	Occasion	Mech	On condition maint	Occasion, Inspect, clean or replace as necessary	DGS : buffer gas filter system
1 year	Occasion	Mech	Scheduled overhaul	Occasion planned to clean the heat exchanger from trend analysis	A-42820 TI-42812, TI-42820
1 year	Occasion	Mech	On condition maint	1) Occasion planned inherently with yearly borescope inspection, perform vibration analysis and trend analysis during compressor shutdown and cool-down pump running.	M-42850 P-42850
1 year	Occasion	Mech	Scheduled overhaul	Occasion planned inherently with half life inspection, clean strainer or replace if any damage.	TE-3200 - Fuel gas strainer

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
1 year	Occasion	Mech	Failure finding	1) Check compressor drain piping to ensure no blockage or valve leakage before start	K-3200-Compressor drain valve
1 year	Occasion	Mech	On condition maint	1) Occasion planned inherently with bore scope inspection, inspect blade condition and belt tension or replace belt if required. 2) Visual check belt condition	A-3260 fan blade Drive belt
4 years	Occasion	Mech	Scheduled overhaul	Clean and check condition of ventilation fan blades	TE-3200, Enclosure ventilation fan
4 years	Occasion	Mech	Scheduled overhaul	Overhaul the starter by replacement by spare module then send to factory for recondition	TS-3200
4 years	Occasion	Mech	On condition maint	Visual inspection wash tank	T-42605 T-42600
4 years	Occasion	Mech	Scheduled overhaul	1) Occasion planned inherently with half life inspection, disassemble & clean or replace damaged parts if required. 2) Shutdown status inherent indicates the integrity	EI-3222 EI-3252
4 years	Occasion	Mech	On condition maint	Replace DGS when exhibit the rejection limit from the analysis	DGS
4 years	Occasion	Mech	Scheduled overhaul	Occasion planned inherently with half life inspection, to clean RO	RO-42726 RO-42727 PDSL-44713 & 14
4 years	Occasion	Mech	On condition maint	1) During compressor shutdown, check condition, performance on the cool-down pump. 2) Record PDI 42855 during cool down pump running. 3) Schedule replace or clean filter	P-42850 PDI-42855
4 years	Occasion	Mech	Failure finding	Occasion scheduled clean & calibrate	PI-42230
4 years	Occasion	Mech	Failure finding	During compressor shutdown, to observe and record PDI42855 in order to monitor filter blockage or deteriorated.	F-42855 PDI-42855
8 years	Occasion	Mech	Scheduled overhaul	Occasion, planned inherently with GG exchange to clean and inspect internal tubing.	A-3230 TI-3230/TI-3232 A-3260
8 years	Occasion	Mech	Scheduled overhaul	Occasions planned inherently with GG exchange, clean and inspect, replace damaged parts if required.	TEK-3200 , Flame arrester
10 years	Off line	Mech	Corrective maint	1) Monitor pump discharge pressure during water wash and plan to repair when washed pressure drop	P-42610
6 months	Occasion	Elect	Scheduled overhaul	Service motor bearings and observe any noise and vibration as standard motor maintenance.	M-42500 M-42501

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
1 year	Occasion	Elect	On condition maint	1) Clean or replace heater.	H-42605
1 year	Occasion	Elect	Scheduled overhaul	Grease motor bearings and observe any noise and vibration.	M-42502
4 years	Occasion	Elect	Scheduled overhaul	Occasion planned to replace bearings from trending as necessary	M-42805 M-42810
4 years	Occasion	Elect	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSH-42844
4 years	Occasion	Elect	Failure finding	Function test to verify the function	M-42502
daily	On line	Instr	On condition maint	1) Monitor lube oil temp in oil tank (TI 42100) 2) to monitor and record oil temp at oil passage.	TCV-42147 TI-42100
monthly	On line	Instr	On condition maint	Visual check for noise and temp profile from internal passing leak	PSV-3220 PSV-3258
6 months	Occasion	Instr	Failure finding	Surge stimulation to verify anti-surge function	Anti-surge function, FE-3220, FT-3221, FT-3220, EI-3220
1 year	Occasion	Instr	Scheduled overhaul	1) Occasion to clean the heat exchanger from trend analysis 2) Calibrate and function test instrument	A-42145 TI-42144 TI-42145
1 year	Occasion	Instr	On condition maint	Check calibration or Replace Temp sensors if required.	T5 element
1 year	Occasion	Instr	Failure finding	1) Clean and check calibration of the vibration switch. 2) Verify the function.	VSH-42820 VSH-42825
1 year	Occasion	Instr	Failure finding	1) Function test & calibration of flame detectors, heat detectors, gas detectors, etc. 2) Check and test fire extinguishing system. 3) Verify Fire suppression are ready for function	BE-42500/01 HD-42500-04 GD-42500
1 year	Occasion	Instr	Failure finding	1) Inspect and Clean fire dampers. 2) Lubricate and function test on fire dampers and actuator and related system.	TE-3200-Fire damper
1 year	Occasion	Instr	Failure finding	1) Clean, check calibration and function test	LAHH-3211 LG-3213
1 year	Occasion	Instr	Failure finding	1) Check calibration and function test.	GD-42700 GD-42710 GD-42720 GD-42730
1 year	Occasion	Instr	Failure finding	1) Occasion, When compressor shutdown, record PDI 42855 during cool down pump running. 2) If stuck or improper reading, to calibrate or replace is required.	PDI-42855
1 year	Occasion	Instr	Failure finding	Check calibration and function test.	TSH-42823
1 year	Occasion	Instr	Failure finding	Check calibration and function test.	PSH-42725

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	SDV-3214
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	PT-3223 PI-3222
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	TT-3220 TI-3220
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	PT-3226 PT-3225 PI-3224
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	TT-3223 TT-3222
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	PALL-3253
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	PALL-3254
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	TAHH-3253
1 year	Occasion	Instr	Failure finding	Occasion planned inherently with borescope inspection, check calibration and function test.	PAHH-3259
1 year	Occasion	Instr	Failure finding	Function test (1 yearly)	SDV-3210 SDV-3211 PDH-3212, inlet check valve
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test or overhaul if required.	P-2160
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test or overhaul if required.	XV-42215 P-42216-18
4 years	Occasion	Instr	Scheduled overhaul	To scheduled overhaul fuel metering valve train	FV-42215 FV-42220 XV-42225 XV-42230
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, clean & check calibration and function test.	LSH-42211 LG-42210
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	SDV-42200
4 years	Occasion	Instr	Scheduled overhaul	1) Replace all instrument filters. 2) Check calibration or function test. 3)	SOV-42251 PCV-42252

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
				Inspect and clean the valves and orifices as necessary	SOV-42253 SOV-42256 PCV-42257 XV-42250 FV-42255
4 years	Occasion	Instr	Failure finding	Function test and calibrate	HD-42500 to 04 TSHH-42501 TSHH-42502
4 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test.	LSLL-3242
4 years	Occasion	Instr	Failure finding	1) Occasion planned inherently with half life inspection, 2) Check calibration and function test.	LV-3214 SDV-3214
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration	SDV-3210 SDV-3211 PDH-3212, inlet check valve PI-3210
4 years	Occasion	Instr	Failure finding	Occasion, planned inherently with half life inspection, check calibration and function test.	FV-3220
4 years	Occasion	Instr	Failure finding	1) Occasion planned inherently with half life inspection, check calibration and function test.	XV-3221
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	XV-42211
4 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test. 2) Measure & record oil pressure	PCV-42813 PI ???
4 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	PCV-42840
4 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, clean and calibrate.	TV-42821 TIC-42821
4 years	Occasion	Instr	Scheduled overhaul	1) Occasion check any blockage and clean the vent lines. 2) Inspect, clean and adjust needle valves properly. 3) Inspect and clean rupture disc or replace if required.	DGS FV-42710 FV-42711 PSE-42720 PSE-42723
4 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	PDCV-42710
4 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	PCV-42725
4 years	Occasion	Instr	Scheduled overhaul	1) Yearly borescope inspection, inspect & clean spark plugs. 2) Replace if spark gap out of tolerance. 3) Function test on	TE-3200, Igniter

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
				igniter system.	
4 years	Occasion	Instr	Failure finding	Clean and function test	PSLL-42843
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	LSL-42801
4 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	PSL-42812
4 years	Occasion	Instr	Failure finding	Occasion, planned inherently with half life inspection, check calibration and function test.	PT-42215 PT-42216 PT-42217 PT-42218
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	TSL-42211 TI-42210
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSL-42173 PI-42172
4 years	Occasion	Instr	Failure finding	Record data for trending.	PI-42172
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDSH-42171 PI-40172
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDI-42170
4 years	Occasion	Instr	Failure finding	Occasions planned inherently with half life inspection, clean & inspect, replace damaged parts if required.	ARV-42162
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSV-42160
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSV-42110
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDSL-42713 PDSL-42715
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDT-42710
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDSL-42710
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDAHH-229
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	LV-3244 SDV-3242

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
4 years	Occasion	Instr	Failure finding	Clean, check calibration and function test on Occasion planned inherently with half life inspection.	LAHH-3241 LG-3243
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	SDV-3241 SDV-3242
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	FV-3250 FE-3250
4 years	Occasion	Instr	Failure finding	Occasion Check calibration and function test.	SDV-3211
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, clean and check calibration.	FT-3200
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PT-42842 PSL-42842 PAL-42842 PI-42842 PI-42841
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSL-42851
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PSH-42831
4 years	Occasion	Instr	Scheduled overhaul	1) Operation inherent indicates the status 2) Occasion to lubricate the moving parts and function test	FDP-42500 FDP-42501 FDP-42502 SOV-42500 SOV-42501 SOV-42502
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	TSHH-42502 TSH-42501
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	FSL-42500 FSL-42501 FSL-42502
4 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	PDSH-42501 PDSHH-42502 PDSHH-42503
4 years	Occasion	Instr	Failure finding	1) Occasion planned inherently with half life inspection, check calibration and function test.	PDSL-42508 PDI-42507
4 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test. 2) Lubricate moving parts and function test	FDP-42503 FDP-42504 SOV-42503 SOV-42504
8 years	Occasion	Instr	On condition maint	Clean, disassemble to inspect and replace damaged parts Calibration test as required as standard RV certification.	PSV-3210
8 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half	PSV-42210

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
				life inspection, clean and calibrate.	
8 years	Occasion	Instr	Scheduled overhaul	Occasions planned inherently with GG exchange, clean & inspect and calibrate.	PSV-42246
8 years	Occasion	Instr	Scheduled overhaul	Occasions planned inherently with GG exchange, clean and check calibration.	PSV-3220 PSV-3258
8 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test. 2) Static or dynamic test for probe sensitivity calibration.	VE-42402-5 VE-2840-3 ZE-42400-1 ZE-42840, 2
8 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test. 2) Check probe sensitivity on vibration exciter.	VE-42300 VE-42301 VE-42302
8 years	Occasion	Instr	Scheduled overhaul	1) Occasion planned inherently with half life inspection, check calibration and function test. 2) Check probe sensitivity on vibration exciter.	VE-42400 VE-42401
8 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	SE-42840
8 years	Occasion	Instr	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration and function test.	SE-42301-2 SE-42401-3
8 years	Occasion	Instr	Corrective maint	Occasion planned inherently with half life inspection, check calibration and function test.	TCP System
8 years	Occasion	Instr	Corrective maint	Occasion planned inherently with half life inspection, check calibration and function test.	Vibration system "Bently Nevada System"
8 years	Occasion	Instr	Failure finding	Clean, check diameter, calibrate and function test.	FE-3220 FT-3221 FT-3220 EI-3220
8 years	Occasion	Instr	Failure finding	Occasion planned inherently with half life inspection, check calibration and function test.	BDV-3251 RO-3251
monthly	On line	Specialist	On condition maint	Perform vibration analysis, trend analysis on related parameters and performance analysis.	TE3200-Vibration monitoring system
3 months	On line	Specialist	On condition maint	1) Take lube oil sampling and oil analysis. 2) Recommended RBOT analysis of oil degradation if possible	T-42100-Oil sampling
3 months	On line	Specialist	On condition maint	1) Take lube oil sampling and oil analysis. 2) Recommended RBOT analysis of oil degradation is required. 3) Metal chip analysis	T-42800-Oil sampling
3 months	On line	Specialist	On condition maint	1) Monitor VSV angle and observe its trending in order to predict time for VSV replacement. 2) Measure and record GG performance	TE-3200 - VSV control



Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
1 year	Occasion	Specialist	Scheduled overhaul	Carry out RBI fan blades to check any cracks or damage.	A-42145 A-42845
1 year	Occasion	Specialist	On condition maint	1) Collect transient vibration during startup and shutdown in order to perform rotor dynamics analysis on Occasion planned inherently with yearly borescope inspection, 2) Occasion planned to replace the bearing as necessary	TE-3200-Vibration monitoring system
1 year	Off line	Specialist	Scheduled overhaul	Perform bore scope inspection	TE-3200
4 years	Occasion	GE	Scheduled overhaul	Occasion half life inspection: to overhaul (done by GE).	P-42110
4 years	Occasion	GE	Scheduled overhaul	Occasion during half life inspection, pump overhaul done by GE.	P-42160 PSV-42160
4 years	Occasion	Specialist	Scheduled overhaul	Occasion planned inherently with half life inspection, check calibration or replace VSV control.	TE-3200 - VSV control
4 years	Occasion	Specialist	Scheduled overhaul	1) Occasion planned inherently with half life inspection, inspect air intake and exhaust ducts, all frame structures. 2) Check condition or replace all seal gaskets, acoustic thermal insulation. 3) Check any drain piping to ensure no any plug. 4 Check any loose part or corroded	TE-3200, Air intake and Exhaust Ducts
4 years	Occasion	Specialist	On condition maint	1) Perform vibration monitoring. 2) Opportunity planned to inspect couplings condition and looseness and check alignment.	K-3200 PGT-3200 Vibration monitoring system
4 years	Occasion	Specialist	On condition maint	1) Occasion planned inherently with half life inspection, check calibration and function test.	A-3230, fan blade
4 years	Off line	Specialist	On condition maint	Blade inspection & assessment	TE-3200
4 years	Occasion	GE	Scheduled overhaul	Half life inspection, equipment overhaul done by GE.	T-42130
4 years	Occasion	Specialist	On condition maint	Carry out RBI shell thickness	D-3210 D-3240
4 years	Occasion	Specialist	On condition maint	Occasion planned inherently with half life inspection, clean and inspect.	A-3230 A-3240
5 years	On line	Specialist	On condition maint	Carry out RBI (Note: Stainless steel drum.)	D-42210
5 years	On line	Specialist	On condition maint	Carry out RBI oil tank thickness.	T-42100
5 years	On line	Specialist	On condition maint	Carry out RBI tank shell thickness	T-42800
6 months	Occasion	Specialist	Failure finding	Stimulate surge to verify the Anti surge function	Anti surge function, FV-3220
6 months	Occasion	Specialist	Failure finding	Stimulate surge to verify anti surge integrity	Anti surge function, FV-3250, FE-3250
8 years	Occasion	GE	Scheduled overhaul	Occasion GG exchange to replace pump (done by GE).	P-42140 P-42141 P-42242 P-42103

Interval	On line Off line Occasion	Resource	Maintenance strategy	Work description	Tag
8 years	Occasion	Specialist	On condition maint	Occasion planned inherently with half life inspection; perform internal cleaning and inspection (RBI, check wall thickness and corrosion rate, etc.).	D-3210 D-3240
8 years	Occasion	Specialist	On condition maint	Visual inspection and clean if necessary	T-42800
8 years	Off line	Specialist	Scheduled replacement	Exchange GG , Inherently , inspect power turbine for life assessment	Gas generator
8 years	Occasion	GE	On condition maint	Life assessment during removing/exchange GG	Power turbine
10 years	Off line	Instr	Redesign	Redesign to alarm instead of shutdown	TT-3220 TI-3220
10 years	Off line	Specialist	Redesign	Redesign to relocate buffer gas off-take point to the final discharge line	DGS
10 years	Off line	Specialist	Redesign	Consider to cool inlet air temp or steam injection as power augmentation	Gas generator
10 years	Off line	Specialist	Redesign	Redesign online water wash to extend off line water wash interval	TE-3200
10 years	Off line	Specialist	Redesign	Redesign gas compressor on line washing using ZOC 27	K-3200-Compressor

6. Manpower and Resources

Estimated manpower and resources for each turbocompressor in loop of 8-10 years life cycle are as follows:

Turbocompressor (only one unit - TEK3200): **Avg. Man-hr/year (loop of 8-10 years life cycle)**

Prod	255.5
Mech	1813.7
Elect	7.8
Instr	202.2
Specialist	173.2

Note: Manpower will be based on estimated effective work only (not included preparation, downtime and contingency works).

4 years interval will be turnaround period that may be extended to 5-6 years.



บริษัท อีควิตี้ เซอร์วิสเชส แอนด์ โซลูชั่นส์ จำกัด
801/138 หมู่ 8 ถนนพหลโยธิน
ต.คูคต อ.ลำลูกกา จังหวัดปทุมธานี 12130.
โทร. 0 2992 5040 โทรสาร 0 2992 5041
โทร. 0 2998 7308 โทรสาร 0 2998 7309
อีเมล : esspower@esspower.com
manorom@bteng.com

Equity Services & Solutions Co., Ltd
801/138 Moo 8 Phaholyothin Rd.,
Ku-Kod, Lamluka, Prathumthanee12130
Tel : 0 2992 5040, Fax : 0 2992 5041
Tel : 0 2998 7308, Fax : 0 2998 7309
Email : esspower@esspower.com
manorom@bteng.com

7. Attachments

All information of Turbocompressor - RCM had been kept in a spread sheet (Excel file)
Additionally concerned information also kept together in the same CD addressed accordingly.

- Drawings: PFD, P&ID
- Data Sheets: Gas Turbine & Compressor
- Drawings: Schematic Diagrams (LM2500 & NP compressor)
- Cross-sectional drawings: Gas turbine & Compressor
- Daily Log Sheets
- Lube Oil Analysis
- GT Compressor Cleaning


NOTES

- 1 - NON-SHAFT CHECK VALVE
- 2 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 3 - COMPRESSORS K 3320 & K 3350 ARE GAS TURBINE
- 4 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 5 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 6 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 7 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 8 - CANCELLED
- 9 - DRAIN POT CLOSE TO T 3300
- 10 - VALVE FOR FUEL GAS LINE PHASE BEFORE START UP
- 11 - HIGH POINT
- 12 - DELETED
- 13 - FV PASS VALVE FOR PRESSURIZATION
- 14 - FV PASS VALVE FOR PRESSURIZATION
- 15 - FV PASS VALVE FOR PRESSURIZATION
- 16 - FV PASS VALVE FOR PRESSURIZATION
- 17 - FV PASS VALVE FOR PRESSURIZATION
- 18 - FV PASS VALVE FOR PRESSURIZATION
- 19 - FV PASS VALVE FOR PRESSURIZATION
- 20 - FV PASS VALVE FOR PRESSURIZATION
- 21 - FV PASS VALVE FOR PRESSURIZATION
- 22 - FV PASS VALVE FOR PRESSURIZATION
- 23 - FV PASS VALVE FOR PRESSURIZATION
- 24 - FV PASS VALVE FOR PRESSURIZATION
- 25 - FV PASS VALVE FOR PRESSURIZATION
- 26 - FV PASS VALVE FOR PRESSURIZATION
- 27 - FV PASS VALVE FOR PRESSURIZATION

INSTRUMENTS SUPPLIED BY COMPRESSOR SUPPLIER ARE SHOWN AS :




OR



NOTES:

- 1 - NON-SHAM CHECK VALVE
- 2 - WITH HAT THE STRAINER ON REMOVABLE SPOOL PECE
- 3 - COMPRESSOR K 3350 & K 3350 HE GAS TURBINE
- 4 - COMPRESSOR K 3320 & K 3350 HE GAS TURBINE
- 5 - DRIVER ON COMMON SHAFT
- 6 - PROVISION FOR CORROSION INHIBITOR INJECTION
- 7 - FOR MACH INJECTION
- 8 - HIGH POINT
- 9 - DELETED
- 10 - NOT USED
- 11 - NOT USED
- 12 - F48 SINGLE VALVE INSTRUMENT HOOK-UP
- 13 - F48 DOUBLE VALVE INSTRUMENT HOOK-UP
- 14 - NOT USED
- 15 - NOT USED
- 16 - NOT USED
- 17 - ESD 3 SHUTDOWN THRU PLC SYSTEM SUPPLIED BY COMPRESSOR
- 18 - VENDOR FOR ITEMS MARKED (X)
- 19 - THE FOLLOWING I/O LIST DETAILS INCLUDED FOR EACH MOTOR OF A3360 (TOTAL 4 NOS.)
 - ON/OFF STATUS
 - FAULT STATUS FOR TYPICAL DETAILS REFER TO LEGEND SHEET.
 - WITH OPERATING PRESSURES GREATER THAN OR EQUAL TO 110 BAR.G.
 - IF TEMPERATURE FALLS BELOW 45°C AT FV-3350 INLET, HYDRATES MAY FORM. HENCE TAI 3362 IS SET @ 47°C.
- 20 - DURING START-UP A3360 MOTORS MAY HAVE TO BE STOPPED, TO PREVENT HYDRATES ACROSS FV-3350 DUE TO EXCESSIVE COOLING.
- 21 - NOT USED
- 22 - LOOP WITH PRES/TEMP COMPENSATION USING PI-3351 AND TI-3350
- 23 - DELETED.
- 24 - DELETED
- 25 - DELETED
- 26 - RO3351 4" 900# DANIEL R37
- 27 - SPACER REQUIRED.
- 28 - PRESSURISATION OF C-3610 WHEN IT IS ALREADY LINGUP TO C-3610 WITH TRAIN 2 COMPRESSOR SHALL NOT BE MADE IN ORDER TO AVOID DAMAGE TO FIRST BLOCK VALVE ON C-3610

INSTRUMENTS SUPPLIED BY COMPRESSOR SUPPLIER ARE SHOWN AS :  OR 




NOTES

- 1 - NON SJM CHECK VALVE
- 2 - REMOVABLE STRAINER
- 3 - INSULATION FOR PERSONNEL PROTECTION (PP)
- 4 - OPERATING PRESS. 22-28 barg
- 5 - DESIGN PRESS. 60 barg
- 6 - DESIGN TEMP. 32 °C MAX 9°C
- 7 - HIGH POINT
- 8 - REMOVABLE SPOOL
- 9 - PROVISION FOR MECHANICAL INJECTION
- 10 - LOOP WITH PRESSURE/TEMPERATURE COMPENSATION
- 11 - FLANGES TAPPING
- 12 - LG TO COVER ALL SET POINTS
- 13 - DELETED
- 14 - VALVE LOCATED AT HIGH POINT IN LINE AND FREE DRAINING
- 15 - TO BE USED FOR SEAL/BUCKET GAS DURING COMMISSIONING ON AIR/N₂
- 16 - REMOVABLE SPOOL
- 17 - PROVISION FOR CORROSION INHIBITOR INJECTION
- 18 - LOOP WITH PRESSURE/TEMPERATURE COMPENSATION USING PT-4015 AND TT-4070
- 19 - LIQUID DRAIN FROM AUTOMATIC TRAPS INSIDE GAS COMPRESSION SYSTEM

* OR  BY COMPRESSOR SUPPLIER

⊗ COMPRESSOR SUPPLIER SHUT DOWN LOGIC SYSTEM





NOTES

- 1 - NON SLAM CHECK-VALVE.
- 2 - REMOVABLE STRAINER.
- 3 - COMPRESSORS K-3420 & K-3450 ARE GAS TURBINE DRIVEN ON COMMON SHAFT.
- 4 - PROVISION FOR CORROSION INHIBITOR INJECTION.
- 5 - HIGH POINT.
- 6 - DELETED
- 7 - PROVISION FOR MeOH INJECTION
- 8 - FLANGE TAPPING.
- 9 - DELETED
- 10 - LOOP WITH PRESSURE/TEMPERATURE COMPENSATION.
- 11 - LG TO COVER ALL SET POINTS.
- 12 - FOR SUPPLY OF AIR/2 TO SEAL GAS SYSTEM. CONNECTION REQUIRED DURING COMMISSIONING ONLY, REMOVE SPOOL AND BLANK AFTER COMMISSIONING.
- 13 - DELETED
- 14 - FV 3451 LOCATED AT HIGH POINT : FREE DRAINING ON EITHER SIDE
- 15 - SPOOL PIECE.
- 16 - DELETED


LEGEND :

- * VENDOR SUPPLIED ITEMS
- ⊗ VENDOR LOGIC SYSTEM.





NOTE 4: PIPING INSULATION IS I.N.R.P. SCOPE OF SUPPLY



NOTE 1:
INSTRUMENTS FROM 1 TO 200
SEE DMS 300/00

NOTE 2:
INSTRUMENTS FROM 201 TO 400
SEE DMS 300/00


NOTE 3:
LIMIT OF SUPPLY SEE DMS 300/00


NOTE 4:
SEE DMS 300/00

NOTE 5:
INSTRUMENTS FROM 401 TO 600
SEE DMS 300/00


ELECTRICAL INSTRUMENTS TYPICAL LOOPS

FIELD	INSTRUMENT	LOOP	DESCRIPTION
FIELD 1	RTD-101	101	TEMPERATURE
	PT-101	101	PRESSURE
	FT-101	101	FLOW
	ST-101	101	STOP
FIELD 2	RTD-201	201	TEMPERATURE
	PT-201	201	PRESSURE
	FT-201	201	FLOW
	ST-201	201	STOP
FIELD 3	RTD-301	301	TEMPERATURE
	PT-301	301	PRESSURE
	FT-301	301	FLOW
	ST-301	301	STOP
FIELD 4	RTD-401	401	TEMPERATURE
	PT-401	401	PRESSURE
	FT-401	401	FLOW
	ST-401	401	STOP






◆NOTE : INSTRUMENTS POINT OUT BY AN ASTERISK ARE PROCESSED BY THE C.C.P.




AS-BUILT



AS-BUILT


> 10000 RPM CORR : ALARM
 > 10300 RPM TRIP
 < 1700 RPM at t > 30 sec TRIP
 < 4500 RPM at t > 90 sec TRIP

ALARM
 10000 RPM
 CORR.




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE

TRANSIT. PIECE




POWER TURBINE


TRANSIT. PIECE



POWER TURBINE

TRANSIT. PIECE





AS-BUILT



LOCATION	THAILAND-B-STP	QUANTITY	2 UNITS	1/6/90	1	0
UNIT	COMPRESSION					
ENGINEERING						
JOB N°						
DESIGNATION				DATE	BY	APPR REV
1	Manufacturer NUOVO PIGNONE/GENERAL EL. Manufacturing plant FLORENCE (ITALY) / EVENDALE (OMC)					
2	Type and size PGT 25 Functional design : Units ☐ Package ☒					
3	Service : Continuous ☒ Intermittent ☐ ISO classification : A ☐ B ☐ C ☐ D ☒ (ISO 917)					
4	Driven equipment CENTRIFUGAL COMPRESSOR Transmission DIRECT COUPLING					
5	SERVICE CONDITIONS					
6	Simple cycle ☒ SEE MATERIAL REQUISITION					
7						
8	Driven equipment power requirement SEE COMPRESSOR D.S. kW AND JOB SPEC. THAI B1 PP 12.06.101					
9	Nominal power (ISO conditions) 22670 kW SECTION 18- ATTACHMENT 2					
10	Driven equipment speed SEE COMPRESSOR D.S. RPM SITE DATA					
11	Power turbine speed 6300 (100%) RPM Altitude SEA LEVEL					
12	Starts : Frequency (ISO 3977) I ☒ II ☐ III ☐ IV ☐ Barometer 1013 m bar					
13	Auxiliaries starting : Manual ☐ Automatic ☐ (S) Ambient temperature : Normal 29 °C					
14	Remote control ☐ Maxi 34 °C, Mini 25 °C, Design 32 °C					
15	Operation : Attended ☐ Unattended ☒ Humidity at design temperature 70%					
16	Remote control ☐ (S) Wind speed 26 m/s					
17	Minimum continuous operation between maintenances 4320 hr Atmospheric air					
18	Dust > 10u g/m³					
19	< 10u g/m³					
20	SHOP TESTS / INSPECTION PAINTING Corrosion by : SALT LADDED AIR					
21	Shop inspection ☒ Simple ☐ Witnessed ☐ Standard ☐					
22	By certification agency ☐ test ☐ test ☐ Other ☒ Location : Indoor ☐ Heated ☐					
23	Manufacturer standard test ☒ JOB SPEC. THAI B1 PP 12.06.101					
24	Mechanical test ☐ Winterisation ☐ Tropicalisation ☒					
25	Performance test ☐ SECTION 10 Area classification (2)					
26	Test with driven equipment ☐ SHIPMENT Starting : Local ☐ Remote ☐ (S)					
27	Dismantling after test (a) ☐ Standard ☐ (2) SEE JOB SPEC. THAI B1 PP 12.06.101					
28	Spare rotor fit in (turbine) ☐ Sea boxing ☒					
29	Spare rotor mech test (turbine) ☐ Long term ☐ SECTION 2.2					
30	Spare gas generator part test (a) ☐ AS PER AVAILABLE UTILITIES					
31	APPLICABLE JOB SPEC. Cooling water : NOT AVAILABLE					
32						
33	ACCESSORIES SUPPLIED BY MANUFACTURER (M) OR OTHER (O)					
34	Turbine baseplate M Pressure - bar g					
35	Driven equipment baseplate M Allowable ΔP - bar					
36	Compressor cleaning system M Temperature - °C					
37	Anchor bolts M Handling device M Allowable ΔT - °C					
38	Driven equipment M Fire protection equipment M Steam : NOT AVAILABLE					
39	Special tools M Pressure - bar g					
40	High speed coupling M Temperature - °C					
41	Coupling guards M Batteries and chargers Instrument air :					
42	Inlet system M Motor control center M Pressure 5 TO 8 bar g					
43	Exhaust system M Local control panel M Temperature 42 °C					
44	Turbine enclosure M Control module M Dew point - 20 °C					
45	Driven equipment enclosure (3) Electricity					
46						
47	Fuel treatment system - Vibration analysis M					
48						
49	Control					
50	SEE JOB SPEC. THAI B1 PP 12.06.101 SECTION 18- ATTACHMENT 4					
51	Remarks : (1) test conditions to be indicated					
52	(2) IF NECESSARY TO MEET JOB REQUIREMENTS					
53	(3) AS PER VENDOR STANDARDS / SPECIFICATIONS OF POWER TURBINE AS A MINIMUM					
54	(4) SEE JOB SPECIFICATIONS IN THAI B1 PP 12.06.101 SECTION 5.0					
55						

Total or partial reproduction and/or utilization of this document are forbidden without prior written authorization of the owner



LOCATION	THAILAND-P-STR	TE-3300				4
UNIT	COMPRESSION					3
ENGINEERING		QUANTITY: 2 UNITS				2
JOB N°						1
						0
			DESIGNATION	DATE	BY	APPR
				1/6/90		REV

PERFORMANCE (SITE CONDITIONS) (1) (4)					
Point		Nominal	Maxi	Mini	RATED
Dry bulb temperature	°C	29	34	23	32
Turbine shaft power	kW	20942	20107	21903	20435
Turbine shaft speed	RPM	6500	6500	6500	6500
Heat rate	KJ/KWH kcal/kWh	10198	10333	10070	10277
Air flow	kg/s	62.15	60.39	64.13	61.09
Exhaust flow	kg/s	63.84	62.04	65.90	62.75
Firing temperature	°C	NA	NA	NA	NA
First stage rotor blade metal temperature	°C	NA	NA	NA	NA
Exhaust temperature	°C	542	547	537	545
Gear losses	kW	—	—	—	—
Net power at driven equipment coupling	kW	20942	20107	21903	20435
INLET LOSS	mm H ₂ O	150	150	150	150
EXHAUST LOSS	mm H ₂ O	100	100	100	100
FUEL SYSTEM					
Type : Gas ☒	Gas fuel analysis (% mole) IN/OUT TREAT SKID				
Treatment required by Manufacturer:	Composition	Normal	Starting	other	
	H ₂	10.868		0.866	
	H ₂ O	1.014		1.014	
	CO	—		—	
	CO ₂	114.7		22.541	
Filtration by vendor ☐	H ₂ S	—		—	
Filter number	H ₂	—		—	
Filter material	CH ₄ C ₁	73.251		64.985	
Filtration micron	CH ₄ C ₂	5.427		5.408	
ΔP clean/maxi / bar	CH ₄ C ₃	2.491		2.857	
Filter body material	CH ₄ iC ₄	0.701		0.704	
	CH ₄ mC ₄	0.610		0.689	
Stainless steel piping ☒	CH ₄ iC ₅	0.290		0.277	
Downstream filters ☒ Complete system ☐	mC ₅	0.183		0.187	
	(2) C ₆	0.217		0.225	
	(3) C ₇ +	0.247		0.247	
		100.00	100.00	100.00	
	Molecular weight	22.999		35.319	
	Cp/Ov				
	LHV kJ/kg				
	MW kJ/kg				
	Heck. max	31.5		31.5	
	TEMP (IN/OUT) °C	64	84		64 84
	Dew point °C				
	84° MAXIAL - 91° MAX WITH INLET TEMP OF 77°				
	Gas for pneumatic starter ☒ SAME AS FUEL GAS				
	Pressure		31.3	bara	
	Temperature 61.41 °C Dew point			°C	
Remarks: (1) FOR GAS TURBINE PERFORMANCE VERSUS DRIVEN EQUIPMENT					
POWER REQUIREMENT REFER TO UNIT SHAFTLINE POWER					
EXHAUST FLOW PAGES 6 TO 8					
(2) C ₆ MW = 84 S.G. = 0.688 (3) C ₇ MW = 130.8 S.G. = 0.770					
(4) EXPECTED VALUES (5) NOT AVAILABLE					

Total of partial reproduction and/or utilization of this document and technical without prior written permission of the owner.

314



CUSTOMER	THAILAND	TE 3300					4
LOCATION	THAILAND						3
UNIT	COMPRESSION						2
ENGINEERING		QUANTITY: 2 UNITS					1
JOB N°				1/6/90			0
			DESIGNATION	DATE	BY	APPR	REV

CONSTRUCTION									
1									
2	Model PGT 25 Type				Power turbine : type AXIAL				
3	Number of shafts 2				Number of stages 2				
4	Direction of rotation (facing output coupling)				Number of stages with variable angle nozzles ✓				
5	Clockwise ☒ Counter-clockwise ☐				Minimum speed 3250 RPM Trip speed 7100 RPM				
6	Critical speeds	1ST	2ND	3RD	Maximum tip speed (nominal speed) 420 m/s				
7	Gas generator lateral	22000	25000		Maximum temperature 824 °C				
8	Power turbine lateral				Maximum pressure 3.5 bar				
9	System torsional (1)	3261	22556		Rotor : Solid ☐ Built up ☒				
10					Casing split : Horizontal ☐ Vertical ☒				
11	Gas generator : Type 7LM2500 GE				Number of openings for inspection				
12	Compressor : Type AXIAL				Bearings : Type TILTING PADS				
13	Number of stages 16				Number 2 Manufacturer GLACIER				
14	Number of stages with variable angle nozzles 6-16				Thrust bearing : Type TILTING PADS				
15	Compression ratio 20 : 1				Manufacturer GLACIER				
16	Minimum speed 4950 RPM Trip speed 10300 RPM				Load 16000 dell capacity 20 000 dell				
17	Maximum tip speed 390 m/s								
18	Maximum temperature 460 °C				Flanges size and orientation (facing output coupling)				
19	Maximum pressure 19 bar				Inlet : Size x				
20	Rotor : Solid ☐ Built up ☒				Orientation : ↑ ☒ ↓ ☐ → ☐ ← ☐ Other ☐				
21	Casing split : Horizontal ☒ Vertical ☐				Exhaust : Size x				
22	Number of openings for inspection 16				Orientation : ↑ ☒ ↓ ☐ → ☐ ← ☐ Other ☐				
23	Combustors : Type ANNULAR								
24	Single ☒ Multiple ☐ - Number				Materials				
25	Gas fuel ☒				Inlet casing 316 L S. Steel				
26	Temperature stratification N.A. °C				Gas generator				
27	Number of nozzles per combustor 30				Compressor : Casing M152 Steel - INCO 718				
28	Number of opening for inspection 8				Stator/Rotor blades Ti-6Al-4V/A286 / Ti-6Al-4V/A286				
29	Gas generator turbine(s) : Type AXIAL				Wheel/Shaft Ti-6Al-4V/INCO 718 / INCO 718				
30	Number of stages 2				Combustor HASTELLOY X - HS188				
31	Maximum tip speed 480 m/s				Gas generator turbine				
32	Maximum temperature N.A. °C				Stage	1	2	3	4
33	Rotor : Solid ☐ Built up ☒				Stator blade	X-40	Reni 80		
34	Casing split : Horizontal ☐ Vertical ☒				Rotor blade	Reni 80	Reni 80		
35	Number of openings for inspection 16				Wheel	INCO 718	INCO 718		
36	Bearings : Type ROLLER				Power turbine				
37	Number 3 Manufacturer N.A.				Stage	1	2	3	4
38	Thrust bearing : Type BALL				Stator blade	FSX 414	FSX 414		
39	Number 1 Manufacturer N.A.				Rotor blade	IN 738	U 500		
40	Load N.A. dell Capacity N.A. dell				Wheel	6 Mo V Steel			
41					Output shaft 6 Mo V Steel				
42									

Total & Remarks	WEIGHTS AND DIMENSIONS			
		Weight kg	Dimensions m	Total shipping weight
	Complete gas turbine	40000	3.5x8.65x3.65	Largest item : Weight
	Gas generator	2200	2=3.0 Ø=21.3	Dimensions x x
	Power turbine	8000	1.5x2x2.5	Erected dimensions x x
	Air filtration	6500	51x5.7x1.85	Maximum maintenance weight 4000
	Exhaust	13000	3.7x2.2x1.3	
Remarks:				
(1) POWER TURBINE + CENTRIFUGAL COMPRESSOR				

Total or partial reproduction and/or utilization of this document are forbidden without prior written authorization of the owner



CUSTOMER	TOTAL	ITEM	TE 3400					4
LOCATION	THAILAND		TE 3300					3
UNIT	COMPRESSION							2
ENGINEERING								1
JOB N°						1/6/90	1/1	0
				DESIGNATION	DATE	BY	APPR	REV

1	LUBE OIL SYSTEM (API 814)							
2	Oil system : FOR GAS GENERATOR				Heater : type NOT PROVIDED			
3	Separate for driven equipment				Manufacturer \ Power \ kW			
4	& power turbine (1)							
5	Mounting on baseplate Separate console				Filter : Single Dual			
6	Capacity m³/hr Pressure bar				Filter material INORGANIC FIBERS			
7	Relief valve setting 6.9 bar				Filtration 12 μ ABSOLUTE micron			
8					ΔP : Clean/max 0.2 / 1.4			
9	Pumps Main Standby Emergency				Filter body material AISI 316 L			
10	Type GEAR							
11	Driver ACC. G. B.				Switch valve : Number INTEGRAL WITH FILTER			
12	Mounting \				Type Manufacturer			
13	Flow m³/hr 4.7				Material			
14	Pressure bar 7							
15	Power kW \				Cooler : Single Dual (Air cooled)			
16	Speed RPM \				Type AIR COOLED Manufacturer AERPO MARELLI			
17	Material \				Duty 100 % Surface 8			
18	Standby pump shutdown : Manual Automatic				Fouling factor 0.000172 m²°C/W			
19	Bearing scavenge pumps				Material AISI 316 L			
20	Type GEAR Number 4							
21					Accumulator Capacity NOT PROV. l			
22	Reservoir in baseplate Separate (ON BASEPLATE)				Type Manufacturer			
23	Material ST-52 AISI 316 L Coating -							
24	Capacity 0.45 m³ Retention 0.35 min				Stainless steel piping : 316 L 321			
25					Downstream filter Complete system			
26								
27								

ACCESSORIES

29	Inlet system : Number of filtration stages 2					Starting system : Manual ☐ Automatic ☒			
30	Item	Make	Type	Material	ΔP mm WC	Semiautomatic ☐ Purge time			
31	Prefilter	AAF	M 80	FIBERGLASS	8	Electric motor ☐ Diesel ☐ Hydraulic ☐			
32	Filter	AAF	XL 90	FIBERGLASS	18	Expansion turbine ☒ Other ☐			
33	Silencer	AAF	BAFFLES	AISI 316 L	18	Make GARRET Type AXIAL TURBINE Power 7.5 kW			
34	Ducting	AAF		AISI 316 L					
35	Expansion joint	AAF		GLASS FIBRE		Shaft turning device (%) Manual ☐ Automatic ☐ (2)			
36	Manometer					Make Type Power kW			
37	Housing					(%) NOT REQUIRED			
38	Anti-icing system ☐ Method					Fire protection equipment ☒			
39	Support structure ☒ Height of air intake +33.130m					Gas detection in turbine enclosure ☒			
40	(By Vendor)					Number of gas detectors AS PER JOB SPEC			
41	Exhaust system : Height of stack +43.000 m					Fire detection in turbine enclosure ☒			
42	Item	Make	Type	Material	ΔP mm WC	Type of fire detectors Number AS PER JOB SPEC			
43	Expansion joint	AAF		COMPOSITE		Fire protection with CO2 ☐ Halon ☒			
44	Silencer	AAF	BAFFLES	A387G11	70				
45	Ducting	AAF		A387G11		Other accessories ☒ AS PER JOB SPEC			
46	Heat recovery								
47	Stack	AAF		A387G11					
48	Manometer								
49	Support structure ☒ By Vendor								
50									

51 Remarks : (1) See separate data sheet
 52 (2) VENDOR TO SPECIFY TYPE / LOCATION / TYPE OF DRIVE

53
 54
 55

Total or partial reproduction and/or utilization of this document are forbidden without prior written authorization of the owner



UNIT (COMPRESSION)		QUANTITY 2 UNITS		DESIGNATION		DATE		BY		APPROV		REV	
ENGINEERING						1/6/90		N				C	
JOB N°													
INSTRUMENTS AND CONTROLS (2)													
1	Panels	By vendor	Mounting	Particularity	Alarms and shutdowns See Schedule 12								
2	Cage	☒	LOCAL	☐ (1)	Switches ☒ Type								
3	Scarcing	☒	LOCAL	☐ (1)	Annunciator ☒ Type ON CRT								
4	Control	☒	"	☐ (1)	Manufacturer								
5					Acoustic annunciator ☒ Type								
6	Governor : Standard ☐ Other ☒ ESTIMON MODEL:				Defect		Alarm		Shutdown				
7	Manufacturer G.E. Type MARK IV				Standby oil pump operating		☒		☐				
8	Constant speed ☐ Variable speed ☒				Low oil pressure		☒		☒				
9	Mini/Maxi speed 3900 / 6825 RPM				Over speed trip		☒		☒				
10	Control signal : Pneumatic ☐ Hydraulic ☐				Low fuel pressure		☒		☐ NO				
11	Electronic ☒ Manual ☐				Over temperature (EXHAUST)		☒		☒				
12	Mini/Maxi signal				Temperature control failure		☒		☐				
13	On signal failure : Mini speed ☒ Maxi speed ☐				Combustor flame out		☐		☒				
14	Constant speed ☐				High inlet air filter ΔP		☒		☒				
15	Limit switch for generator drive				Starter failure		☒		☐				
16	Regulation NEMA class				or low oil level		☒		☐				
17	Controlled process variable				High oil filter ΔP		☒		☐				
18	Method of control Δ = 20 mA				High oil temperature cool-out		☒		☒				
19					Bearing over temperature		☒		☒				
20	Safety fuel shut off valve ☒				Gas turbine vibration		☒		☒				
21	Possible test during operation ☐ NO				Driven equipment vibration		☒		☒				
22													
23	Alarm and shutdown switches												
24	To alarm : Switch closes ☐ Switch opens ☒												
25	To shutdown : Switch closes ☐ Switch opens ☒				Temperature Instruments								
26	Enclosures : Weather proof ☐ Explosion proof ☒				Indicators : Make (1) CRT Type								
27	Possible test during operation NO				Recorders : Make Type								
28	Alarm switches ☐ Shutdown switches ☒				Mounting		Indicator		Recorder (3)				
29	SPEED INDICATION ON CRT				Air inlet, outlet comp		☒		☒ NO				
30	SPEED SENSOR : Number 3 ON PT 2 ON GG				Compressor discharge		☒		☐				
31	Manufacturer AIRPAX Type MAGNETIC TYPE				Inter turbine		☒		☐				
32	Locations 3 ON PT SHAFT CASING				Exhaust		☒		☒ NO				
33	2 ON GG AUX GEAR BOX				Oil reservoir		☒		☐				
34	Vibration detectors : Number 2 ON PT 3 ON GG				Oil cooler outlet temp		☒		☐				
35	Manufacturer BELL & HOWELL Type SYSMIC (PT)				Bearings		☒		☐				
36	METRIX Type ACCELEROMETER (GG)				Fuel		☐		☐				
37	LOCATION PT ON SHAFT SUPPORT CASING												
38	GG ON AX. WHP. FRONT FRAME ON												
39	AX. COMPRESSOR REAR FRAME, ON TURB. MID FRAME												
40	TOTAL UTILITY CONSUMPTION SEE SOS 23965/4 REV 02												
41	Cooling water : Flow	NOT AVAILABLE		m³/hr	Electricity								
42	Heat duty			kcal/hr	Starting		DC Power		AC Power				
43					Operation								
44	Steam : Nominal flow	NOT AVAILABLE		kg/hr	Standstill								
45	Maxi flow			kg/hr									
46													
47	Fuel : Nominal flow			kg/hr	Instrument air flow				kg/hr				
48	Maxi flow			kg/hr									
49													
50													
51	Remarks : (1) Separate listing												
52	(2) VENDOR TO COMPLETE AND REFER TO JOB SPEC NO THAT B1 PP 12-06-101												
53	SECTION 18.0 - ATTACHMENT 6												
54	(3) RECORDER IS NOT PROVIDED												
55													

Total or partial reproduction are forbidden without prior authorization of the owner

Pa Ha

TURBO COMPRESSOR UNIT SHIFTLINE POWER BALANCE

*VENDOR TO SPECIFY
MAX OPERATING CASE
(I.E CASE FOR WHICH
195 POWER IS HIGHEST)

OPERATING CONDITIONS

- Ambient temperature
- Atmospheric pressure
- Relative humidity

CENTRIFUGAL COMPRESSOR

1st stage

AT SUCT. FLANGE

- Weight flow $\dot{V}$ INCL. FUEL GAS
- Inlet temperature
- Inlet pressure
- Outlet pressure
- Outlet temperature
- Polytropic efficiency
(including internal losses:
balance drum leakage ...)
- Polytropic comp. power
- Tolerance on above power
- Max. Polytropic comp. power
- Mechanical losses
- Other allowances:

- Power reqd at comp. shaft

2nd Stage

- Weight flow AT DISCH. FLANGE
- Inlet temperature
- Inlet pressure
- Outlet pressure
- Outlet temperature
- Polytropic efficiency
(including internal losses:)
- Polytropic comp. power
- Tolerance on above power
- Max. polytropic comp. power
- Mechanical losses
- Other allowances

- Power read at comp. shaft

Total power required INCL. 4%
at DRIVER shaft API TOLER.)
at operating speed

OPERATING CASES

UNITS

⑤

°C

bar

%

kg/h

°C

bar abs

bar abs

°C

%

Kw

%

Kw

Kw

Kw

Kw

Kg/h

°C

bar abs

bar abs

°C

%

Kw

%

Kw

Kw

Kw

Kw

Kw

at

r.p.m.

WOR MAX
29 32

232940

26

23

53.7

105

74.1

3780

30

30

30

17260

226440

50

52.7

112

126

64.7

3420

30

30

30

30

17260

17350

6440

REVISION

0

1

2

3

4

date

1/6/90

by

Checked

Authorization of the owner

Use of this document is forbidden without prior written permission

Total or partial reproduction and/or use is forbidden

OPERATING CASES

GE-290X

- Mechanical efficiency
- Mechanical losses

Total power required
at gear box L.S. shaft
at operating speed

GAS TURBINE

Speeds

- Gas generator
- Power turbine

ISO continuous power at above
speeds

Ambient temp. correction

- Correction factor
- Power output reduction

Altitude correction

- Correction factor
- Output reduction

Compressor fouling loss

- Correction factor
- Output reduction

Intake loss

- Pressure drop
- Correction factor
- Output reduction

Exhaust loss

- Pressure drop
- Correction factor
- Output reduction

Direct deductible auxiliaries

- Shaft driven lube oil pump
- Shaft driven generator
- Others: HYDRAULIC OIL PUMP
GRAVENAGE PUMP

Other allowances:

-

-

Net continuous available power
output at turbine coupling

UNITS	⑤	○			○	○
η						
Kw						
Kw						
at						
r.p.m.						
r.p.m.	29° 32'					
9285	9302					
6440	6440					
Kw	2305	2310				
η	-68	-9.2				
Kw	2148	2095				
η	/	/				
Kw	/	/				
η	/	/				
Kw	/	/				
mm W.G.	150	150				
η	-2.2	-2.2				
Kw	-483	-484				
mm W.G.	100	100				
η	-5	-5				
Kw	-114	-113				
Kw	INCLUDED					
Kw	/					
Kw	INCLUDED					
Kw						
Kw	2038	2035				

REVISION	0	1	2	3	4
date	1/6/90				
by					
Checked	HI				

Notes on this page are for information only and should not be used for design or construction purposes. All dimensions are in inches unless otherwise specified.

OPERATING CASES

	UNITS	(5)	(1)					
Heat rate	KJ/kWh	11022	10296					
Firing temperature	°C	N.A.	N.A.					
Material temperature	°C	N.A.	N.A.					
- 1st stage nozzle GG		N.A.	N.A.					
- 1st stage blading GG								
- 1st stage blading PT								
Exhaust temperature	°C	1540	543					
Compressor inlet air flow	Kg/s	61	64					

REVISION

0

1

2

3

4

date

1/6/90

by

Checked

I-BI-PP-12-08-1101

14/15
16/90

CUSTOMER TOTAL	ITEM K3320/3350				1
LOCATION THAILAND-B-STR	K3320/3350				2
UNIT COMPRESSION					3
ENGINEERING	QUANTITY: 2 UNITS				4
JOB N°		1/6/90	M		0
	DESIGNATION	DATE	BY	APPS	REV

1	Manufacturer :	NUOVO PIGNONE	Manufacturing plant :	FLORANCE
2	Size and type :	2BCL603	Functional design :	Units ☐ Package ☒
3	Service :	NATURAL GAS	Continuous ☒ Intermittent ☐	ISO classification A ☐ B ☐ C ☐ D ☒
4	Driver Type :	GAS TURBINE		(ISO 3977)

5	RATED OPERATING CONDITIONS				APPLICABLE SPECIFICATIONS
6	Operating case	(5)	(10)		SEE MATERIAL REQUISITION
7	Gas handled	CASE	(5)	(10)	
8	Capacity (1.013 Bar A.M.S.E) Sm ³ /hr				AUD JOB SPEC NO THAI BI PP 12.06.101
9	Specific weight (1.013 Bar A.M.S.E) kg/m ³				SECTION 18: ATTACHED 2
10	Weight capacity INCL. FUELS kg/hr	232940	256460		SITE DATA
11	Suction Capacity m ³ /hr	10.018	10.322		Altitude SEA LEVEL
12	Suction Pressure (1) bar a	23	23		Barometer 1013 m bar
13	Conditions Temperature °C	26	26		Ambient temperature : Normal 29 °C
14	Compressibility factor	0.937	0.931		Maxi 34 °C, Mini 23 °C, design 32 °C
15	Pressure (1) bar a	112	112		Humidity at design temperature 70 %
16	Discharge Max temperature °C	126	126		Wind speed 26 m/s
17	Conditions Compressibility factor	0.928	0.916		Atmospheric air
18	Guarantee case	YES	NO		Dust > 10µ g/m ³
19					< 10µ g/m ³
20					Corrosion by : SALT LADEEN AIR

20	SHOP TEST / INSPECTION		PAINTING		
21	Shop inspection (2) by control agency	☐	Standard	☐	Installation : Indoor ☐ Heated ☐
22	Tests : Following SP-MEC-035 page 4	☐	(3) (4) Other	☒	Under roof ☐ Outdoor ☒ Off shore ☒
23	Hydrostatic test	☐	☒	JOB SPECIFICATION	Winterisation ☐ Tropicalisation ☒
24	Helium test	☐	☐	THAI BI PP 12.06.101	Area classification
25	Leak test	☐	☒	SECTION 10	Startling : Local ☒ Remote ☐
26	Mechanical test : Single ☐ Tander ☐	☐	☒	SHIPMENT	
27	Performance test :	☐	☒	Standard	
28	FOR DETAILS OF SHOP TEST /	☐	☐	Sea boxing	☒
29	INSPECTION SEE JOB SPEC	☐	☐	Outdoor storage	☐
30	THAI BI PP 12.06.101	☐	☐	AS PER APPLICABLE	
31	SECTION 12 & 13			JOB SPEC	AVAILABLE UTILITIES
32					Cooling water : NOT AVAILABLE

33	ACCESSORIES BY MANUFACTURER (M) OR OTHER (O)				
34	Base plate	M	Process piping		Available Δ P - bar
35	Foundation bolts	M	Inter stages piping		Temperature - °C
36	Driver	M	Safety valves		Δ T - °C
37	Main gear	M	Cooling water piping		Steam : NOT AVAILABLE
38	Gear between casings	-	Check valve		Pressure - bar a
39	Transmission guard		Instrumentation	M	Temperature - °C
40	Low speed coupling	M	Local panel	M	Instrument air :
41	High speed coupling	M	Antisurge	M	Pressure 5 TO 8 bar a
42	Coupling guards	M	Control system	M	Temperature 42 °C
43	Soundproof enclosure		Special tools	M	Dev point -20 °C
44	Barring device		Spare parts	M	Electric supply :
45	Suction filter	M			AC/DC Volts Phase Hertz
46	Silencer		Other		
47	Coolers	(7) M	As per job specification		
48	Moisture separator	-	THAI BI PP 12.06.101		Control
49	Lube oil unit	M	Section 3.0		SEE JOB SPEC THAI BI PP 12.06.101
50	Seal oil unit	M			SECTION 18.0 ATTACH 4

51 Remarks: (1) Measured at limit of supply (2) Following SP-MEC-035 page 4 (3) not witnessed (4) witnessed

52					
53	(7) LIFE	AIR COOLERS			
54					
55					

Total or partial reproduction and/or use of this document are forbidden without prior written authorization of the owner



CUSTOMER TOTAL		ITEM K3220/K3250								4	
LOCATION THAILAND B STR		- K3320/K3350								3	
UNIT COMPRESSION										2	
ENGINEERING		QUANTITY: 2 UNITS								1	
JOB N°						7/6/90		JH		0	
				DESIGNATION		DATE		BY		APPR REV	

OPERATING CONDITIONS										
1										
2	Operating cases	(1)		(2)		(3)		(4)		
3	Guarantee point									
4	Compressor casing	2 BCL 603		2 BCL 603		2 BCL 603		2 BCL 603		
5	Compression section	1ST 2ND		1ST 2ND		1ST 2ND		1ST 2ND		
6	Gas handled									
7	Flow (1.013 BAR A, 15.5°C) Sm³/h									
8	Weight Flow AT SUCT. FLANGES kg/h	180330	135065	174830	132434	209310	212654	269100	212463	
SUCTION CONDITIONS (1)										
10	Volume flow m³/h	3144	2163	7320	3360	10643	13938	10622	4934	
11	Pressure (5) bar a	23	27	23	50.4	23	45.2	23	45.2	
12	Temperature (3) °C	64	50	26	50	64	50	64	50	
13	Relative humidity %	100	100	100	64	100	100	100	100	
14	Molecular weight	22.53	22.33	22.65	22.65	22.43	22.33	22.35	22.33	
15	Cp/Cv	AS PER BURS EQUATION								
16	Compressibility factor	AS PER BURS EQUATION								
DISCHARGE CONDITIONS (1)										
18	Volume flow m³/h	5634	2303	4695	2250	6710	2454	6657	2451	
19	Pressure bar a	43	100.5	51.4	100.5	46.2	90.5	46.2	90.5	
20	Temperature °C	132	125	99	119	131	120	131	120	
21	Cp/Cv	AS PER BURS EQUATION								
22	Compressibility factor	AS PER BURS EQUATION								
23	Flow AT DISCH. FLANGES Kg/h	192654	172746	137434	169330	221022	201546	220216	201352	
24	Pressure ratio	2.037	2.133	2.235	1.994	2.009	2.002	2.009	2.001	
25	Head (2) (FLANGE) m	3640	4230	4050	3337	3120	3330	3180	3400	
26	Efficiency (2) (FLANGE) %	77.3	70.4	75.1	70.2	74.1	68.4	74.2	68.4	
27	Gas power kW	6470	6425	6130	5750	7355	6945	7335	6940	
28	Compressor shaft power kW	12950		11930		14360		14340		
29	Drive shaft power kW	12950		11930		14360		14340		
30	Compressor speed RPM	6160		5380		6380		6380		
31	Drive shaft speed RPM	6160		5380		6380		6380		
32	Surge limit: flow m³/h	6400	3165	6025	2940	6715	3315	6715	3315	
33	AT Speeds ABOVE RPM	6160	6160	5380	5380	6380	6380	6380	6380	
34	Discharge pressure bar a	SEE CURVES								
35	Performance curve N°	SOS 21832								
36	NOTE:	☒ PLANT FLOW + FUEL GAS ☒ PLANT FLOW + FUEL GAS + LEAKAGES FROM LABYRINTHS ☒ PLANT FLOW + LEAKAGES FROM LABYRINTHS - CONVENIENCE FLOW								
CONTROL										
39	Method	Suction throttling ☐		From to		By-pass ☐		From to		
40		Speed variation ☒		From to		Other ☐				
41	Action	Automatic ☒		Manual ☒		Local ☒		Remote ☒		
42	Signal	Nature:		Localization:		Function:				
43	Treatment	Pneumatic ☐		Electronic ☒		Hydraulic ☐				
ANTISURGE (4)										
45	Method	By-pass ☒		From DISCH to SUCT		Discharge to atmosphere ☐				
46	Signal	Nature:		Localization:		Function:				
47	Correction	Pressure ☐		Temperature ☐		Other ☐				
48	Treatment	Pneumatic ☐		Electronic ☒		Hydraulic ☐				
49	(6) FOR ANY CASE, SUCTION PRESSURE MAY VARY BETWEEN 23 BAR A AND 28.7 BAR A									
50	(7) FOR ANY CASE, GAS ANALYSIS MAY BE IN THE RANGE OF COMPOSITIONS STATED IN SHEET									
51	Remarks:	(1) At compressor flange ☒		At limit of supply ☐		18, 18A, 18B				
52	(2) Polytropic ☒ Adiabatic ☐ (3) EXTREME TEMPERATURE MAY RISE UP TO 77°C AT									
53	1ST STAGE INLET AND 55°C AT 2ND STAGE INLET									
54	(4) ONE PER STAGE TO PREVENT HYDRATE FORMATION									
55	(5) SUPPLIER TO CONSIDER A ΔP OF 1 BAR BETWEEN 1ST STAGE DISCH. & 2ND STAGE SUCT.									

16/17
7/6/90

CUSTOMER TOTAL	ITEM K3220/3250				4
LOCATION THAILAND B-STR	K3320/3350				3
UNIT COMPRESSION					2
ENGINEERING	QUANTITY: 2 UNITS				1
JOB N°		7/6/90			0
	DESIGNATION	DATE	BY	APPR	REV

1	OPERATING CONDITIONS									
2	Operating cases	(5)		(6)		(7)		(8)		
3	Guarantee point	X	X							
4	Compressor casing	2BCL 603		2BCL 603		2BCL 603		2BCL 603		
5	Compression section	1ST	2ND	1ST	2ND	1ST	2ND	1ST	2ND	
6	Gas handled									
7	Flow m ³ /h									
8	Weight Flow AT SUCTION FLANGES kg/h	232940 ^o	240221 ^o	198130 ^o	203375 ^o	172070 ^o	130731 ^o	230730 ^o	234634 ^o	
9	SUCTION CONDITIONS (1)									
10	Volume flow m ³ /h	10418	4830	9031	4128	6925	3433	10576	4915	
11	Pressure (5) bar a	23	52.7	23	46.3	23	50.2	23	45	
12	Temperature (3) °C	26	50	64	50	26	50	64	50	
13	Relative humidity %	100	67	100	100	100	64	100	100	
14	Molecular weight	22.65	22.65	25.31	25.24	25.0	25.0	25.31	25.24	
15	Cp/Cv	AS PER BURS EQUATION								
16	Compressibility factor	AS PER BURS EQUATION								
17	DISCHARGE CONDITIONS (1)									
18	Volume flow m ³ /h	5933	2751	5593	2282	4182	1934	6701	2930	
19	Pressure bar a	53.7	112	47.3	100.5	51.2	100.5	46	90.5	
20	Temperature °C	105	126	132	125	98	119	131	121	
21	Cp/Cv	AS PER BURS EQUATION								
22	Compressibility factor	AS PER BURS EQUATION								
23	Flow AT DISCH FLANGES kg/h	246122	226440	210936	190503	135382	167470	243036	222278	
24	Pressure ratio	2.335	2.125	2.078	2.147	2.226	2.002	2.0	2.011	
25	Head (2) (FLANGE) m	10060	5195	8630	8330	8440	7550	8180	7585	
26	Efficiency (2) (FLANGE) %	74.1	69.7	76.8	70.4	74.9	70	72.9	67.5	
27	Gas power kW	8780	8420	6390	6230	5420	5135	7390	7005	
28	Compressor shaft power kW	17260		12820		10600		14450		
29	Drive shaft power kW	17260		12820		10600		14450		
30	Compressor speed RPM	6440		5910		5500		6170		
31	Drive shaft speed RPM	6440		5910		5500		6170		
32	Surge limit : flow m ³ /h	6975	3330	6140	3075	5550	2750	6535	3290	
33	At Speeds ABOVE RPM	6440	6440	5910	5910	5500	5500	6170	6170	
34	Discharge pressure bar a	SEE CURVES								
35	Performance curve	SOS 21332								
36										
37										

38	CONTROL (SEE PAGE 15/16)									
39	Method	Suction throttling ☐	From	to	By-pass ☐	From	to			
40		Speed variation ☐	From	to	Other ☐					
41	Action	Automatic ☐	Manual ☐	Local ☐	Remote ☐					
42	Signal	Nature :	Localization :			Fuction :				
43	Treatment	Pneumatic ☐	Electronic ☐			Hydraulic ☐				
44	ANTISURGE(4) (SEE PAGE 15/16)									
45	Method	By-pass ☐	From	to	Discharge to atmosphere ☐					
46	Signal	Nature :	Localization :			Fuction :				
47	Correction	Pressure ☐	Temperature ☐			Other ☐				
48	Treatment	Pneumatic ☐	Electronic ☐			Hydraulic ☐				

51	Remarks: (1) At compressor flange ☒ At limit of supply ☐									
52	(2) Polytropic ☒ Adiabatic ☐									
53	NOTES OF SHEET 15/16 ARE VALID									
54										
55										

Total or partial reproduction and/or utilization of this document are forbidden without prior written authorization of the owner.

7/18
6/90

CUSTOMER TOTAL	ITEM K3220/K3250				4
LOCATION THAILAND B STR	K3330/K3350				3
UNIT COMPRESSION					2
ENGINEERING	QUANTITY: 2 UNITS				1
JOB N°					0
	DESIGNATION	DATE	BY	APPR	REV

OPERATING CONDITIONS									
1	Operating cases		(9)		(10)				
2	Guarantee point								
3	Compressor casing		2RCL 608		2RCL 608				
4	Compression section		1ST	2ND	1ST	2ND			
5	Gas handled								
6	Flow (1.013 BAR a., 15.5°C) Nm³/h								
7	Weight Flow at SUCT. FLANGES kg/h		230640	234835	256060	264555			
8	SUCTION CONDITIONS (1)								
9	Volume flow	m³/h	16533	4474	10322	4768			
10	Pressure	(5) bar a	23	45	23	52.6			
11	Temperature	(3) °C	64	50	26	50			
12	Relative humidity	%	100	100	100	70			
13	Molecular weight		25.28	25.23	25.0	25.0			
14	Cp/Cv		AS PER RWRS EQUATION						
15	Compressibility factor		AS PER RWRS EQUATION						
16	DISCHARGE CONDITIONS (1)								
17	Volume flow	m³/h	6713	2922	5336	2707			
18	Pressure	bar a	46	90.5	53.6	112			
19	Temperature	°C	131	121	104	126			
20	Cp/Cv		AS PER RWRS EQUATION						
21	Compressibility factor		AS PER RWRS EQUATION						
22	Flow at DISCH. FLANGES	kg/h	243014	222062	274055	249460			
23	Pressure ratio		2.0	2.011	2.330	2.129			
24	Head (2)	(FLANGE) m	8190	7625	5020	8290			
25	Efficiency (2)	(FLANGE) %	72.5	67.6	73.4	69.2			
26	Gas power	kW	7400	7030	8755	8430			
27	Compressor shaft power	kW	7400	7030	8755	8430			
28	Drive shaft power	kW	7400	7030	8755	8430			
29	Compressor speed	RPM	6170		6190				
30	Drive shaft speed	RPM	6170		6190				
31	Surge limit: flow	m³/h	6590	3295	6755	3305			
32	At Speeds ABOVE	RPM	6170	6170	6190	6190			
33	Discharge pressure	bar a	SEE CURVES						
34	Performance curve	N°	SOS 21832						
35									
36									
37									

38	CONTROL (SEE PAGE 15/16)					
39	Method	Suction throttling ☐	From	to	By-pass ☐	From to
40		Speed variation ☐	From	to	Other ☐	
41	Action	Automatic ☐	Manual ☐	Local ☐	Remote ☐	
42	Signal	Nature :	Localization :		Fuction :	
43	Treatment	Pneumatic ☐	Electronic ☐	Hydraulic ☐		
44	ANTISURGE(4)(SEE PAGE 15/16)					
45	Method	By-pass ☐	From	to	Discharge to atmosphere ☐	
46	Signal	Nature :	Localization :		Fuction :	
47	Correction	Pressure ☐	Temperature ☐	Other ☐		
48	Treatment	Pneumatic ☐	Electronic ☐	Hydraulic ☐		

51	Remarks: (1) At compressor flange ☒ At limit of supply ☐
52	(2) Polytropic ☒ Adiabatic ☐
53	NOTES OF SHEET 15/16 ARE VALID
54	
55	

Total or partial reproduction and/or translation of this document are forbidden without prior written authorization of the owner

18/18A

7/6/90

DOPTS

LOCATION THAILAND-B-STR	K3320/3350				4
UNIT COMPRESSION					3
ENGINEERING	QUANTITY: 2 UNITS				2
JOB N°					1
					0
		DESIGNATION	DATE	BY	APPR

GAS ANALYSIS									
1	Analysis %	Weight ☐	Mole ☒						
2	Component	M.W.							
3	OPERATING CASES								
4	STAGE		①	②	③	④			
5			1ST	2ND	1ST	2ND	1ST	2ND	
6	H ₂ O		1.014	0.262	0.157	→ 1.014	0.272	0.833	0.273
7	N ₂		0.868	0.876	0.881	→ 0.868	0.876	0.870	0.876
8	CO ₂		14.700	14.829	14.887	→ 14.700	14.827	14.733	14.830
9	C ₁		73.251	73.516	74.317	→ 73.251	73.829	73.434	73.534
10	C ₂		5.427	5.469	5.475	→ 5.427	5.469	5.435	5.467
11	C ₃		2.491	2.505	2.473	→ 2.491	2.505	2.490	2.500
12	iC ₄		0.701	0.711	0.676	→ 0.701	0.711	0.699	0.700
13	mC ₄		0.610	0.610	0.574	→ 0.610	0.610	0.607	0.607
14	iC ₅		0.290	0.287	0.249	→ 0.290	0.287	0.287	0.235
15	mC ₅		0.183	0.180	0.149	→ 0.183	0.180	0.180	0.173
16	C ₆ (SG = 0.668)	84	0.217	0.209	0.131	→ 0.217	0.209	0.210	0.200
17	C ₇₊ (SG = 0.77)	130.8	0.247	0.146	0.031	→ 0.247	0.145	0.223	0.146
18									
19									
20			(1)	(2)	(1)	(2)	(1)	(2)	
21									
22									

MASS FLOWS (Kg/h)

23									
24	PROCESS FLOW *		172 746	169 830	201 546	201 352			
25	FUEL GAS FLOW		5250	5000	5650	5700			
26	LEAKAGES FLOW		12323	12604	11113	11116			
27	CONDENSATE FLOW		2334	0	2714	2048			
28									
29									
30									
31									
32									

NOTE * AT 2ND STAGE DISCHARGE FLANGE

33									
34									
35									
36									
37									
38									
39									
40	Total								

41	Molecular weight, dry								
42	Molecular weight, wet (3)	22.98	22.83	22.65	22.65	22.98	22.83	22.95	22.83
43	Relative humidity %	100	100	100	64	100	100	100	100
44	Corrosion by	CO ₂							
45	Solids	GAS FROM WELLS THRU SEPARATOR							
46									
47									
48									
49									
50									

51 Remarks: (1) GAS ANALYSIS GIVEN AT 1ST STAGE INLET
 52 (2) SUPPLIER TO SPECIFY GAS ANALYSIS AT 2ND STAGE INLET VERSUS
 53 SELECTED INTERSTAGE PRESSURE AND TEMPERATURE OF 50°C
 54 (3) SUPPLIER TO CONFIRM AVERAGE MOLECULAR WEIGHT
 55

Total or partial reproduction and/or distribution of this document are forbidden without prior written authorization of the owner

I-BI-PP-12.08.1101

BA/18B

/6/90

~~DOPTS~~

CUSTOMER TITLE	ITEM NO. 2320				4
LOCATION THAILAND B-STR	K3320/3350				3
UNIT COMPRESSION					2
ENGINEERING	QUANTITY: 2 UNITS				1
JOB N°					0
		DESIGNATION	DATE	BY	APPR

1	GAS ANALYSIS									
2	Analysis %	Weight ☐	Mole ☒							
3	Component	M.W.								
4	OPERATING CASE		(5)	(6)	(7)	(8)				
5	STAGE	-	1ST	2ND	1ST	2ND	1ST	2ND	1ST	2ND
6	H ₂ O		0.157	→ 1.014	0.264	0.157	→ 1.014	0.274		
7	N ₂		0.881	→ 0.866	0.374	0.880	→ 0.866	0.374		
8	CO ₂		14.887	→ 22.541	22.741	22.834	→ 22.541	22.735		
9	C ₁		74.317	→ 64.985	65.523	65.953	→ 64.985	65.576		
10	C ₂		5.475	→ 5.408	5.451	5.457	→ 5.408	5.451		
11	C ₃		2.473	→ 2.857	2.373	2.836	→ 2.857	2.373		
12	iC ₄		0.676	→ 0.704	0.705	0.679	→ 0.704	0.705		
13	nC ₄		0.574	→ 0.689	0.689	0.649	→ 0.689	0.633		
14	iC ₅		0.249	→ 0.277	0.274	0.237	→ 0.277	0.274		
15	nC ₅		0.149	→ 0.187	0.184	0.153	→ 0.187	0.184		
16	C ₆ (SG=0.688)	84	0.131	→ 0.225	0.216	0.136	→ 0.225	0.216		
17	C ₇₊ (SG=0.77)	130.8	0.031	→ 0.247	0.146	0.030	→ 0.247	0.145		
18										
19										
20			(1)	(2)	(1)	(2)	(1)	(2)	(1)	(2)
21										
22										
23										
24	MASS FLOWS (Kg/h)									
25										
26	PROCESS FLOW #		226440	140508	167470	222278				
27	FUEL GAS FLOW		6500	5250	4600	5700				
28	LEAKAGES FLOW		13781	12867	13311	12356				
29	CONDENSATE FLOW		0	2372	0	2752				
30										
31										
32										
33										
34										
35	NOTE #	AT 2ND STAGE DISCH. FLANGE								
36										
37										
38										
39										
40	Total									
41	Molecular weight, dry									
42	Molecular weight, wet (3)		22.65	22.65	25.31	25.24	25.0	25.0	25.31	25.24
43	Relative humidity %		100	67	100	100	100	64	100	100
44	Corrosion by CO ₂									
45	Solids GAS FROM WELLS THRU SEPARATOR									
46										
47										
48										
49										
50										
51	Remarks: NOTES OF SHEET 18/18A ARE VALID									
52										
53										
54										
55										

Total or partial reproduction and/or translation of this document are forbidden without prior written authorization of the owner.

		GAS ANALYSIS			
1	Analysis &	Weight ☐	Mole ☐		
2	Component	M.W			
3	OPERATING CASE		(9)	(10)	
4	STAGE	-	1ST	2ND	1ST 2ND
5	H ₂ O		0.832	0.274	0.157
6	N ₂		0.868	0.374	0.880
7	CO ₂		22.592	22.701	22.834
8	C ₁		65.150	65.596	65.953
9	C ₂		5.417	5.949	5.457
10	C ₃		2.856	2.363	2.836
11	iC ₄		0.702	0.703	0.679
12	nC ₄		0.686	0.636	0.649
13	iC ₅		0.273	0.271	0.237
14	nC ₅		0.184	0.182	0.153
15	C ₆ (SG=0.688)		0.217	0.210	0.136
16	C ₇₊ (SG=0.77)		0.223	0.146	0.030
17					
18					
19			(1)	(2)	(1) (2)
20					
21					
22					
23			MASS FLOWS (Kg/h)		
24					
25					
26	PROCESS FLOW *		222062	249360	
27	FUEL GAS FLOW		6500	6500	
28	LEAKAGES FLOW		12377	14533	
29	CONDENSATE FLOW		2078	0	
30					
31					
32					
33					
34	NOTE * AT 2 ND STAGE DISCH. FLANGE				
35					
36					
37					
38					
39					
40	Total				
41	Molecular weight, dry				
42	Molecular weight, wet (3)		25.28	25.22	25.0 25.0
43	Relative humidity %		100	100	100 70
44	Corrosion by CO ₂				
45	Solids GAS FROM WELLS THRU SEPARATOR				
46					
47					
48					
49					
50					
51	Remarks: NOTES OF SHEET 1B/18A ARE VALID				
52					
53					
54					
55					

TAI-BI-PP-12-08-101

: 19/20

: 1/6/90



CUSTOMER TOTAL		ITEM K 3320/3350									
LOCATION THAILAND-B-STR		K3320/3350								4	
UNIT COMPRESSION										3	
ENGINEERING		QUANTITY: 2 UNITS								2	
JOB N°										1	
						1/6/90		M		0	
				DESIGNATION		DATE		BY		APPR REV	
CONSTRUCTION											
Casing designation Z BCL 60S				Shaft MATERIAL EQ. TO AISI d3d0							
Direction of rotation (view from driver)				Impellers fitting KEYED & SHRUNK							
CW ☐ CCW ☒				Diameter at impellers				265 mm			
Speed				Diameter at couplings				150 mm			
Maximum continuous 6325 RPM				Shaft ends : tapered ☒ Cylindrical ☐							
Maximum tip speed AT M.C.S. 257.3 m/s											
Critical speed 1 st 2 nd 3 rd				Balance drum MATERIAL EQ. TO ASTM A240 GRAD							
Lateral 3250 11700				Surface 688 / 375 cm² Diameter 360 / 330 mm							
Torsional 3261 22556 27232				Fitting method KEYED & SHRUNK							
Lateral Damped ☒ Tors. Undamped ☒											
Found by : Calculation ☒ Test ☐				Shaft sleeves MATERIAL EQ. TO ASTM A240 GRAD							
				Between impellers ☒ At seals ☒							
Balancing AS PER API 617				Fitting method SHRUNK							
Applicable code Grade											
Static ☐ Dynamic ☒ speed 499 RPM				Labyrinths MATERIAL ALUMINIUM ALLOY							
				Stationary ☒ Rotating ☐							
Overspeed test											
Individual ☒ Complete rotor ☒ speed 7166 RPM				Seals : DRY GAS SEALS "CRANE" 23 AT TAUBER							
* AS PER API MECHAN. RUNNING TEST				API 617 ☒ Figure n° 7							
Allowable vibration level during test * microns				Circulating oil flow — 1/min							
Peak to peak ☒ on shaft ☒				Oil leakage — 1/day							
				Oil supply : From lube ☐ Independent ☒							
Casing MATERIAL EQ. TO ASTM A266 CL. 2				Maximum casing pressure at idle bar							
Cast ☐ Forged ☒ Welded ☐				Possible start up with idle pressure ☐							
Split : Vertically ☒ Horizontally ☐				Buffer gas N/A ☐ Nitrogen ☐							
Thickness 12 mm Corrosion allowance 3 mm				Gas flow : normal kg/h at bar							
Maximum operating pressure R.V.S. (K) 117 barg				Maxi kg/h at bar							
Design pressure 130 barg				Buffer gas used for : start up ☐							
Test pressure : Hydrostatic 195 barg				Normal duty ☒ Running with air ☐							
Helium bar				Buffer gas control ☐							
Maximum operating temperature 200 °C				SETTLING OUTPRESSURE ; SEE SHEET 27/28							
Minimum operating temperature -20 °C				Seal test API 617 ☐ Pressure bar							
Maximum allowable number of impellers 3											
Maximum casing flow ≈ 20000 m³/h				Bearing housings MATERIAL EQ. TO AISI 93d0							
				Bolted to casing ☒ Built in ☐							
				Split HORIZONTALLY							
Number of discharge volutes 2											
				Radial bearings MATERIAL ASTM A266 CL. 3 + HOYT HR							
Diffusers : without vanes ☒ with vanes ☐				Type TILTING PADS Span 2370 mm							
				Diameter 150 mm Length 66 mm							
Impellers MATERIAL EQ. TO ASTM A240 GRAD				Load : Actual 9 bar Allowed 20 bar							
Number 4 + 4 Diameter 720 mm				Individual oil flow 55 l/min Pressure 1.2 barg							
Number of vanes 17 / 15 / 15 outlet angle 40° ± 15°											
Design : Cast ☐ Forged ☒											
Welded ☒ Riveted ☐											
Open ☐ Closed ☒											
Smallest tip internal width 16 mm											
Maximum Mach number at impeller eye 0.4											
BACK TO BACK ARRANGEMENT											
Remarks :				1) VENDOR TO SPECIFY.							
(*) RELIEF VALVE SET											

Total or partial reproduction and/or translation of the owner of this document are forbidden without prior written permission.

20121
16/90

CUSTOMER TOTAL	ITEM K3320/3350				4
LOCATION THAILAND-B-STR	ITEM K3320/3350				3
UNIT COMPRESSOR					2
ENGINEERING	QUANTITY: 2 UNITS				1
JOB N°					0
	DESIGNATION	DATE	BY	APPR	REV

1	CONSTRUCTION (CONTINUED)									
2	Thrust bearing (1) TILTING PADS - DBL ACTION					Forces and moments allowable on flanges (3xSM23)				
3	Location : suction side EXTERNAL RAD. BEARING					SUCTION		DISCHARGE		
4	Type TILTING PADS Make KINGSBURY					Force	Moment	Force	Moment	
5	Diameter 10 1/2" Area 35550 mm²					daN	mdaN	daN	mdaN	
6	Load: Actual 3.2 bar Allowed 27 bar					Axial				
7	Gas thrust ≈ 11500 N					Vertical				
8	Thrust transmitted by coupling ≈ 27800 N					Horiz 90°				
9	Coupling friction coefficient 0.15					SEE				
10	Thrust taken by the balance pistons ≈ 12665 N					SPEC DO.	Force	Moment	Force	Moment
11	Oil flow 20 l/min Pressure ≈ 0.4 bar					THAI BIPP	daN	mdaN	daN	mdaN
12	Lubrication : FLDONED					12.06.201				
13	Thrust collar: Replaceable					AB 7.1.2.5				
14	Thrust load at Surge & MCS: 1100 daN									
15	TOWARD 2ND SUCTION									
16	COUPLINGS					FLANGES AND CONNECTIONS				
17	Attached data sheet		DRIVER							
18	Item					Diam.	Class	Face	Posit.	Speed
19	Make		REUK		1ST SECTION		ANSI			m/s
20	Model		ZTKSU	STD COUPL. X G.F.	Suction	20"	300#	R/S	Down	20
21	Lubrication		YES		Discharge	16"	300#	R/S	UP/DOWN	17
22	Spacer		YES		2ND SECTION					
23	Limited end float		N/A		Suction	16"	300#	R/S	UP/DOWN	14
24	Keyed		DO		Discharge	14"	300#	R/S	Down	11
25	Hydraulic fit		YES							
26	— 1 — 1/2 tools		YES							
27						Service		Diam.	Class	Face
28	MATERIALS EQUIVALENT TO:					Lube oil inlet (2)	2"	150#	RF	
29	Casing : Outer ASTM A226 G2 Inner ASTM A240 G2					Lube oil outlet (2)	5"	150#	FF	
30	Diaphragms ASTM A240 G2 INTERSECTING ASTM A182 F22					LUBE oil inlet (3)	1 1/2"	150#	RF	
31	Impellers ASTM A240 G2					LUBE oil outlet (3)	3"	150#	FF	
32	Yield stress 535 N/mm² Brinell hardness 220 HB					Casing drains	1"	1500#	RJ	
33						Stage drains	N/A	N/A	N/A	
34	Shaft AISI 4340					LUBE OIL VENTS	2"	300#	RF	
35	Balance piston ASTM A240 G2					Liquid injection	N/A	N/A	N/A	
36	Shaft sleeves ASTM A240 G2					Cooling water	N/A	N/A	N/A	
37						Buffer gas	1 1/2"	1500#	RJ	
38	Labyrinths : Impellers AVIOLAL 14					SEAL GAS INLETS	2"	1500#	RJ	
39	Piston "					SEAL GAS (4)	2"	1500#	RJ	
40	Shaft ends "					SEAL GAS (5)	3"	1500#	RF	
41	Bearing housings AISI 9840									
42	Radial bearing babblett 110YT									
43	Thrust bearing babblett AS PER MANUFACTURER STD					WEIGHTS AND DIMENSIONS				
44						Weights kg : Comp.: 33000 Casing outer: 18000				
45	INLET WALLS AND INLET NOZZLES:					Rotor: 2000 Inner Bundle: 15'000				
46	STAINLESS STEEL PLATED EQUIVAL. TO AISI 304					Dimensions mm : shaft height				
47						Casing : Length 3500 Width 2036				
48						Baseplate : Length Width				
49						ROTOR : LENGTH 3062				
50						Sketch attached ☐				
51	Remarks: (1) Axial Forces considered in the most severe operating case									
52	(2) THRUST BEARING ; (3) JOURNAL BEARINGS ;									
53	(4) PRIMARY VENTS ; (5) SECONDARY VENTS.									
54										
55										

Total or partial reproduction and/or utilization of the owner of this document are forbidden without prior written authorization of the owner

COUPLING DATA SHEET

Page : 24/25

Date : 1/6/90



ELEMENT PROJECT

Service **COMPRESSION - GT TO COMPRESSOR** Item n°

APPLICABLE TO: ☒ PROPOSAL ☐ PURCHASE ☐ AS BUILT DATE _____ REVISION _____

OWNER **TOTAL** NO. REQUIRED **2 SETS**

SITE **THAILAND - B - STR** SERVICE **GAS COMPRESSION**

DRIVER TYPE **GAS TURBINE** MANUFACTURER **NUOVO PIGNONE** MODEL **PGT 25**

SERIAL NO. _____ TAG NO. _____
DRIVEN UNIT **CENTRIFUGAL COMP** MANUFACTURER **NUOVO PIGNONE** MODEL **2BCL 608**

SERIAL NO. _____ TAG NO. _____

☒ COUPLING: TYPE **GEAR** MANUFACTURER **RENK TACKE** MODEL **ZTKH** SIZE **90 NP/50**
ASSEMBLY DRAWING NO. **SOM 03443 / 458591**

NOTE: INFORMATION TO BE COMPLETED: ☒ BY VENDOR ☐ BY COUPLING MANUFACTURER.

OPERATING CONDITIONS

1 POWER TRANSMITTED (HP): NORMAL **22670** MAXIMUM CONTINUOUS **25500** **KVA 6225 RPM (1)**

2 SPEED (RPM): MINIMUM ALLOWABLE **3750** NORMAL **6500** MAXIMUM CONTINUOUS **6825** **TRIP 7150**

3 TORQUE **M K2** MAXIMUM CONTINUOUS **44258** MAXIMUM TRANSIENT _____

4 FREQUENCY OF TRANSIENTS (EVENTS/TIME) (2.1.1) _____

APPLICATION FACTOR: ☒ MINIMUM REQUIRED **1.75** ☒ ACTUAL **1.86**

5 AMBIENT TEMPERATURE °C MAXIMUM **34** MINIMUM **23**

ENVIRONMENT (3.5) ☐ DUST ☐ HYDROGEN SULFIDE ☐ _____

LUBRICATION (2.2.9) ☒ CONTINUOUS ☐ FILTRATION

☐ GREASE-PACKED ☐ VISCOSITY _____

☐ OIL-FILLED ☐ PRESSURE _____

☐ NONLUBRICATED ☐ TEMPERATURE _____

☒ FLOW **2/min** NORMAL **20** MAXIMUM _____

6 ESTIMATED EQUILIBRIUM TEMPERATURE WITHIN COUPLING HOUSING: °C
AMBIENT TEMPERATURE °C _____

COUPLING DATA

☒ BOLTING TORQUE (M.K2) (2.1.11.4) **206 Nm** ☒ LUBRICATED ☐ DRY

☐ SHAFT SEPARATION AT OPERATING TEMP. (S.E.) _____ THERMAL GROWTH _____ FROM _____ AMBIENT

☐ MOTOR ROTOR FLOAT ☐ LIMITED END FLOAT (2.2.3) ☐ ELECTRICALLY INSULATED (2.1.12)

☐ MARINE TYPE REQUIRED (2.2.2) ☐ FLEX-HUB TYPE REQUIRED (2.2.2)

☒ DESIGN RATING **50/100 RPM** (2.1.1) **8.6** ☒ MAXIMUM CONTINUOUS TORQUE **Nm** (2.2.8) **44258**

☐ REQUIRED MISALIGNMENT CAPABILITY: (2.1.3)

STEADY STATE: ANGULAR (DEG.) _____ PARALLEL OFFSET **mm/mm** **0.003 (3)** AXIAL **mm/mm** **0.003%**

TRANSIENT: ANGULAR (DEG.) _____ PARALLEL OFFSET **mm/mm** **SAME AS SS** AXIAL **mm/mm** **SAME AS SS**

☒ MAXIMUM ALLOWABLE MISALIGNMENT (2.2.8):

STEADY STATE: ANGULAR (DEG.) **0.083** PARALLEL OFFSET **mm/mm** **0.00145** AXIAL **mm/mm** **± 4**

TRANSIENT: ANGULAR (DEG.) **0.083** PARALLEL OFFSET **mm/mm** **0.00145** AXIAL **mm/mm** **± 4**

DYNAMIC BALANCE: (2.3.3.1) ☐ COMPONENT BALANCE ONLY

☐ COMPONENT BALANCE AND ASSEMBLY CHECK BALANCE ☐ COMPONENT AND ASSEMBLY BALANCE

☐ CHECK SENSITIVITY OF BALANCE MACHINE (2.3.1.3)

☒ MAXIMUM ALLOWABLE RESIDUAL UNBALANCE **GRMM/KG DRIVER END** **1.6** DRIVEN UNIT END **1.6**

☐ MAXIMUM ACTUAL RESIDUAL UNBALANCE (GRMM/KG) DRIVER END _____ DRIVEN UNIT END _____

☐ DIAPHRAGM COUPLING INITIAL DEFLECTION **mm** (2.2.5) ☐ PRESTRETCH ☐ COMPRESSION

☐ DIAPHRAGM COUPLING AXIAL RESONANT FREQUENCY (HZ): (2.3.4) (4.2.4.1) CALCULATED _____ ACTUAL _____

☐ TORSIONAL STIFFNESS **MM/RAD** (2.2.1) **7.55 · 10⁶**

☐ AXIAL STIFFNESS **MM/M** (2.2.3) (2.2.4) **NOT APPLICABLE**

☐ **W K2 · M2** (2.2.2) **2.096**

☐ ANGULAR (MISALIGNMENT) STIFFNESS (LB-IN.) (2.2.3) (2.2.4) **NOT APPLICABLE**

7 (1) BASED ON GAS TURBINE MAXIMUM CONTINUOUS SPEED

(2) BASED ON MAXIMUM CONTINUOUS SPEED

(3) COMBINATION OF OFFSET AND ANGULARITY

COUPLING DATA SHEET

Page : 25126

Date : 1/6/30



SCFM/LIT PROJECT

Service COMPRESSION GT TO COMPRESSOR Item n°

MATERIALS (3.2)

	DRIVE END MATERIALS	DRIVEN END MATERIALS
HUB/FLANGE	17 Gr Ni Mo 6 G	17 Gr Ni Mo 6 G
SPACER	30 Gr Mo V	30 Gr Mo V 9V
SLEEVE	42 Gr Mo 4 V	42 Gr Mo 4 V
DIAPHRAGMS		
DIAPHRAGMS GUARD		
BOLTS	8.8 DIN NT 61514	8.8 DIN NT 61514
NUTS	8 DIN NT 934	8 DIN NT 934

DIAPHRAGM PROTECTIVE COATING (3.4) ☒ VENDOR STANDARD ☐

☒ MATERIAL AND WELD HARDNESS TESTS REQUIRED (4.2.1.3)

INTERNAL TEETH HARDNESS (ROCKWELL C) (2.2.7) ☒ DRIVE END ACTUAL 49^{±11} ☐ DRIVEN END ACTUAL 49^{±11}

EXTERNAL TEETH HARDNESS (ROCKWELL C) (2.2.7) ☒ DRIVE END ACTUAL 51^{±7} ☐ DRIVEN END ACTUAL 51^{±7}

COUPLING HUB MACHINING

	DRIVE END	DRIVEN END
☒ TYPE (INTEGRAL, EXTERNAL, TAPER) (2.1.5) (2.1.7.1)	1:20	1:20
☒ TAPER (1 DEG. 1A, 1/4 IN. PER FT., 3/4 IN. PER FT.) (2.1.8.1) (2.1.8.2)	HYDR.	HYDR.
☐ KEYED OR HYDRAULICALLY FITTED (2.1.7.1) OR FLANGED		
☐ KEYWAY DIMENSIONS AND NUMBER (2.1.9.1)		
☐ NOMINAL BORE DIAMETER	130.55	149.6
☐ INTERFERENCE FIT MAX./MIN. (2.1.7.1)	8.5	7.5
☐ PULLER HOLES		
☒ BALANCING HOLES (2.5.4)		
(1) SEE ATTACHED DRAWING AVAILABLE		

COUPLING GUARD (APPENDIX C)

☒ COORDINATOR (C.2.1) 1510072	☐ OIL MIST COOLING ☐ GAS COOLING
☐ FLANGED CYLINDRICAL ☐ BASE MOUNT (C.3.2)	☒ CONTRACT GUARD TO BE USED DURING SHOP TEST (C.4.5)
☐ AIR TIGHT (C.4.7.1)	
☐ OIL TIGHT (C.2.7)	
☐ SPARK RESISTANT (C.2.9)	
☐ TRANSPARENT WINDOW FOR EACH OIL SPRAY POINT (C.4.8.4)	
VENT-CONNECTION (C.4.3) ☐ 1 INCH NPT WITH FILTER-BREATHER	
☒ 1 INCH FLANGED, RATING & FACING	
☐ PURGE GAS ☐ DRY AIR PURGE (2.3.6) (C.4.4)	
☐ CONNECTION SIZE & TYPE	
☐ SCFM REQUIRED	

ACCESSORIES

☒ PRIME EQUIPMENT SUPPLIER TO FURNISH ONE SET OF PLUG AND RING GAGES (APPENDIX F)	☐ PULLER BY COUPLING MANUFACTURER (4.3.2.4)
☒ DRILL TEMPLATE FOR INTEGRAL FLANGED HUBS BY COUPLING MANUFACTURER (2.1.8)	
☒ TWO-PIECE STOP RINGS BY COUPLING MANUFACTURER (4.3.2.3)	
☒ ONE PUMP SET FURNISHED FOR ALL HYDRAULIC COUPLINGS AT EACH SITE BY COUPLING MANUFACTURER (TO INCLUDE HAND PUMP, PRESSURE GAGE, FITTINGS, AND HOSE) (4.3.2.1)	


APPLICABLE SPECIFICATIONS

☒ API-671, SPECIAL PURPOSE COUPLINGS

PREPARATION FOR SHIPMENT


☒ OUTDOOR STORAGE FOR MORE THAN 3 MONTHS (4.3.1.2)
☒ EXPECTED STORAGE TIME 2 MONTHS
SHIPPING: ☐ DOMESTIC ☐ STORAGE: ☐ INDOOR
☒ EXPORT ☐ OUTDOOR
☐ SEE COUPLING PURCHASE ORDER FOR PRESERVATION, BOXING, AND SHIPPING INSTRUCTIONS

prior written authorization



Identification	Test Description	Purpose of Test
Machine Specific Analysis	Results from the following tests are reviewed by your Machine Condition Analyst and recommendations for your equipment is given with supporting data on each report.	Both Lubricant Condition & Equipment Condition are analyzed based on specific characteristics of your equipment, previous component performance, and test data.
Elemental Analysis	Elemental analysis is performed in accordance with atomic emission spectroscopy (AES). A specific volume of lubricant is energized using an electrical arc. The light frequencies and intensities are measured and reported in parts per million of various elements.	Elemental analysis is useful for identifying contamination, confirming additive content, and indicating system wear. The following elements are analyzed: Fe, Cr, Al, Pb, Sn, Cu, Ag, Ni, Na, V, Cd, Ti, Mo, Ca, Ba, P, Zn, B, K, Mg, and Si.
Water by Karl Fischer (ASTM D-4928)	Results from the following tests are reviewed by your Machine Condition Analyst and recommendations for your equipment is given with supporting data on each report.	Quantification of water contamination - water in a lubricant not only promotes corrosion and oxidation, but also may form an emulsion having the appearance of a soft sludge.
Total Acid Number (ASTM D664)	TAN is determined by titration of a known substance, such as KOH in order to determine an unknown quantity. Weighed samples are titrated using an automatic titration system	TAN of a used lubricant is one measure of its degree of degradation by oxidation.
Total Base Number (ASTM D4739)	TBN is determined by titration of a known substance, such as HCl, in order to determine an unknown quantity. Weighed samples are titrated using an automatic titration system.	TBN of a used lubricant is a measurement of its ability to neutralize the acid using basic buffers.
Infrared Analysis FT-IR	The infrared absorption spectrum of a lubricant furnishes a means of fingerprinting organic compounds and functional groups. Test results are trended and quantitative and qualitative determinations can be made.	Infrared analysis is often used for identifying additives and their concentrations, reaction products, and contamination by organic materials in used lubricants. Oxidation (carboxylic acids and esters), nitrate esters, water, soot, and glycol can be quantified.
Crackle	Eye Dropper test of lubricant on a hot plate heated to 100 deg C to determine presence of water. Detection can be made of water concentration > 800 ppm	This screening test is used by the analysts to check for water contamination and determination of whether more sensitive testing is required to determine more exact concentration.
Viscosity (Kinematic/Oil Bath ASTM D445/446)	ASTM test uses a constant temperature bath. The efflux time is measured between two points. The viscosity is computed by using a calibration constant and the efflux time. Viscosity is reported in centiStokes (cSt) at 40 or 100 deg C.	Viscosity is the single most important property of a lubricant. A reduction usually indicates that the system has been contaminated with a solvent or refrigerant fluid. A significant increase normally is traced to mixture with a high viscosity product, contamination, or oil oxidation. Normal measurement range for 40 deg C is +30% and -20% and for 100 deg C is +20% and -10%.
Fuel Dilution of Diesel Lubricants (ASTM D3524-90) Gas Chromatograph	The sample is mixed with a specific amount of an internal standard. One microliter of the mixture is injected into a 10 meter HP-1 WCOT capillary column, heated at a specified rate, detected via a Flame Ionizing Detector, and the results (in percentages/peak area) are displayed in a report generated from the computer software	Some fuel dilution of the engine oil may take place during normal operation. However, excessive fuel dilution (> 5%) is of concern in terms of possible performance problems. Immediate effects of high fuel dilution are decreased lubricant viscosity resulting in increased wear.
Flash Point (ASTM D92)	The lubricant sample temperature is raised at a constant rate as the flash point is approached. At specified intervals, a small test flame is passed across the cup containing the sample. The lowest temperature at which application of the test flame causes the vapors above the surface of the liquid to ignite is taken as the flash point.	Flash Point indicates the presence of highly volatile and flammable materials in a relatively nonvolatile or nonflammable material. Example: an abnormally low flash point on a test specimen of engine oil can indicate fuel contamination.

Identification	Test Description	Purpose of Test
Rotating Bomb Oxidation Test (ASTM D2272)	The test lubricant, water, and a copper catalyst coil contained in a covered glass container, are placed in a bomb equipped with a pressure gage. The bomb is charged with oxygen to a pressure of 620 kPa, placed in a constant-temperature oil bath set at 150 deg C, and rotated axially at 100 rpm at an angle of 30 deg from the horizontal. The number of minutes required to reach a specific drop in gage pressure is the oxidation stability of the test sample.	Test is used to assess the remaining oxidation test life of in-service lubricants.
Demulsibility (ASTM D1401-96)	40 ml of sample and 40 ml of distilled water are stirred for 5 min. at 54 deg C in a graduated cylinder. The time required for the separation of the emulsion thus formed is recorded or volumes of water, oil, and emulsion remaining after 30 minutes.	Test provides a guide for determining the water separation characteristics of oils subject to water contamination and turbulence.
Pour Point (ASTM D97)	After preliminary heating, the petroleum sample is cooled at a specified rate and examined at intervals of 3 deg C for flow characteristics. The lowest temperature at which movement of the specimen is observed is recorded as the pour point.	Determination of the lowest temperature at which a petroleum product may be used if fluidity is necessary to the application.
%Sulfur (ASTM D4294-90)	A petroleum sample is placed in the beam emitted from an X-ray source. The resultant excited characteristic X radiation is measured, and the accumulated count is compared with counts from previously prepared calibration samples to obtain the sulfur concentration in mass %.	The degree of sulfur concentrations in a petroleum product may be used to qualify the product's processing characteristics or compliance with environmental regulations.
Particle Count (ASTM D4406)	As particles in the lube flow pass a laser, the laser light is blocked allowing individual particles to be counted and sized. The resulting data is a distribution of the concentration of particles in various size ranges.	Since all contaminants in the oil are counted as particles, the particle count includes wear particles, soot, dirt, and other contaminants. This test provides information on lubricant cleanliness.
Foam Test (ASTM D892-95) Sequence I, II, III	A defined volume of air is forced through a set volume of sample lubricant at a specified temperature. The resulting volume of foam is measured	Determination of the foaming characteristics of lubricating oils at specified temperatures. Means of empirically rating the foam tendency and the stability of the foam.
Cone Penetration of Lubricating Grease (ASTM D 217)	A measured amount of grease sample is placed under a cone apparatus. The cone is attached to a gauge that measures from 85-475. The cone is dropped into the grease sample from a specified height and time. The measured amount that the cone penetrates into the grease is dropping point.	This test measures the consistency of grease. Harder grease will have a low NLGI rating number such as 00 or 1. Most industrial greases penetrate in the 265-295 ranges and have a NLGI rating of 2.
Dropping Point of Lubricating Greases (ASTM D566)	A grease sample is heated in the dropping point apparatus. The point where the grease starts separating and the oil drops out of the apparatus is the dropping point. The temperature is measured in degrees Celsius.	This test is a determination of the maximum operating temperature of grease.
% Sediment in Lubricating Oils	An oil sample is well shaken and dissolved in a solvent at a 1:1 ratio. The solvent: oil mixture is well shaken and 100 mls of sample is poured into two centrifuge tubes. The tubes are placed in the centrifuge at opposite ends and spun for 30 minutes. The sediment collected on the bottom is calculated and multiplied by two to give the total percentage of sediment in the oil.	This test is an excellent determination of sediments suspended in lubricating oil. Excessive amounts of sediments can impede oil capability



Recommendations and Notes

Particle count indicates that oil cleanliness level is dirty. Suggest using an off-line filtration system to clean up the oil system. Recommend short sampling intervals of this sample point to monitor the abnormal conditions.

AS / Andy Sitton

			Current Sample			Previous Sample				Alarm Limit Range							
Condition History			Wear	Oil	Cont.	Wear	Oil	Cont.	Wear	Oil	Cont.	Limit Name (Equipment / Oil) :					
FocusLab ID Date sampled Hours on Oil Hours on Unit Bottle ID	Test Method	Result	<div>N</div>	<div>N</div>	<div>A</div>	<div>N</div>	<div>N</div>	<div>N</div>	<div>N</div>	<div>N</div>	<div>N</div>	Engine Turbine Gas GE Jet 530 (PTT E&P)					
			82903			76072			70811								
			03-Sep-07			07-May-07			06-Feb-07								
			Not Given			108187			Not Given								
			110996			108187			106096								
866180			854065			854094											
Wear Condition																	
Wear Element	Method	Unit	RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	RDE fine		RFS coarse		
													U-Caution	U-Action	U-Caution	U-Action	
Iron	D-6595	PPM	0.0		1.4	0.1		0.0		0.9		0.0	>2	>3	>2	>4	
Chromium	D-6595	PPM	0.1		0.0	0.0		0.3		0.0		0.0	>1	>2	>1	>2	
Lead	D-6595	PPM	0.0		0.0	0.0		0.0		0.0		0.0	>1	>2	>5	>8	
Copper	D-6595	PPM	0.1		0.1	0.1		0.1		0.1		0.0	>1	>2	>1	>2	
Tin	D-6595	PPM	4.0		0.0	3.9		0.7		1.7		0.0	>5	>6	>2	>3	
Aluminum	D-6595	PPM	0.3		0.0	0.7		0.0		0.3		0.0	>1	>2	>1	>2	
Nickel	D-6595	PPM	0.0		0.0	0.0		0.0		0.0		0.0	>2	>3	>1	>2	
Silver	D-6595	PPM	0.0		0.3	0.0		0.1		0.0		0.0					
Molybdenum	D-6595	PPM	0.0		0.0	0.0		0.0		0.0		0.0					
Titanium	D-6595	PPM	0.2		0.0	0.4		0.0		0.4		0.0					
Oil Condition												New Oil	L-Action	L-Caution	U-Caution	U-Action	
Viscosity @40°C	D-445	cSt	28.6			29.1			28.5			28.1	<25.3	<26.7	>29.5	>30.9	
Viscosity @100°C	D-445	cSt															
Oxidation	FTIR	Abs	247.3			239.7			153.9								
Nitration	FTIR	Abs	7.8			6.5			6.8								
TAN	D-974	mg KOH/g.	0.36			0.39			0.40			0.49		>0.84	>1.2		
TBN	D-4739	mg KOH/g.															
Contamination												New Oil				U-Caution	U-Action
Water	T-H2O Check SM	% (Wt.)	0.070			0.068			0.064			0.042	>0.123			>0.205	
Sodium	D-6595	PPM	0			0			0			RDE fine					
Silicon	D-6595	PPM	0.2			1.1	0.5		0.0	1.4		0.0	>3	>5	>3	>5	
Additive Element												New Oil					
Boron	D-6595	PPM	0			0			0								
Magnesium	D-6595	PPM	0			0			0								
Calcium	D-6595	PPM	2			0			3								
Barium	D-6595	PPM	4			0			8								
Phosphorus	D-6595	PPM	1424			1462			1506								
Zinc	D-6595	PPM	1			2	0		0	1		0					
Additional Test												New Oil	L-Action	L-Caution	U-Caution	U-Action	
Flash Point	D-3828	°C										>					
Viscosity Index	D-2270																
Other																	

Note: Alarm Limits are variable and dependent upon dataset size and to be used as general guideline.

No Sign or (N) : NORMAL , (C) or (A) : CAUTION (first level warning limit) , (A) or (A) : ACTION required (second level warning limit)

U-Caution : Upper CAUTION Level L-Caution : Lower CAUTION Level


U-Action : Upper ACTION required Level L-Action : Lower ACTION required Level

Accuracy of interpretation and recommendation are based on representatives sample and information supplied

First level warning limit in Upper level and/or Lower level

Second level warning limit in Upper level and/or Lower level

No warranty is expressed or implied for this report.



		Current Sample		Previous Sample			Alarm Limit Range				
FocusLab ID	82903		76072		70811		Limit Name (Equipment / Oil) : Engine Turbine Gas GE Jet 530 (PTT E&P)				
Date sampled	03-Sep-07		07-May-07		06-Feb-07						
Hours on Oil	Not Given		108187		Not Given						
Hours on Unit	110996		108187		106096						
Bottle ID	866180		854065		854094						
Particle Count NAS 1638: Number of Particles Per 100 Milliliter (Counts/100ml)							New Oil	U-Caution		U-Action	
Size Range	No. of Particles	Class	No. of Particles	Class	No. of Particles	Class	Class	No. of Particles	Class	No. of Particles	Class
5-15 microns	69,600	9	13,800	6	16,700	7		<6		<7	
15-25 microns	6,400	8 A	1,300	5	1,500	6					
25-50 microns	1,800	8	300	6	400	6					
50-100 microns	100	8	<100	5	<100	5					
>100 microns	<100	6	<100	3	<100	3					
Particle Count ISO 4406:1999: Number of Particles Per Milliliter (Counts/ml)								<1000		<1500	
Size Range	No. of Particles	Class	No. of Particles	Class	No. of Particles	Class					
>4 microns	2,087	A	413	16	499	16					
>6 microns	584	16	116	14	140	14					
>14 microns	82	14	16	11	19	11					
ISO 4406 Result	18/16/14		16/14/11		16/14/11						

Recommendations and Notes

Particle count indicates that oil cleanliness level is dirty. Suggest using an off-line filtration system to clean up the oil system.

Option Test: Varnish and Sludge Potential Index™ (VsPI™), Testing for Predicting Varnish and Sludge Buildup


		VsPI™ Severity Limit Range Guideline	
VPI™ Value		New Oil	U-Caution
SPI™ Value			U-Action
VsPI™ Value			
Sludge Weight Condition			
	mg/100 ml	mg/100 ml	mg/100 ml
	250	250	250
	200	200	200
	150	150	150
	100	100	100
	50	50	50
	0	0	0

Option Test: RUL (Remain Useful Life), Testing for monitoring Percent Remaining Anti-Oxidant (AO) by ASTM D-6971


		by ASTM D-6971	
% Remaining Antioxidant Additive		New Oil	U-Caution
		100	<50
			<25

Wear Condition

RDE Fine Wear Metal




RFS Coarse Wear Metal




Oil Condition

Viscosity at 40 C in cSt



Viscosity at 100 C in cSt




Lube System Capacity : 450 Liters


Location :

Oil Condition

Oxidation and Nitration




TAN and TBN




Contamination

Contaminant: Water, Fuel and Soot %




Dirt and Dust, NAS



Others


VsPI and AO Additives



Customer Code : 25001

Unit ID Number

: TEK 3200 Preslia 32



Recommendations and Notes

Note abnormal iron detected.
Particle count indicates that oil cleanliness level is in unacceptable range.
Suggest using an off-line filtration system to clean up the oil system.

AS / Andy Sitton

			Current Sample			Previous Sample						Alarm Limit Range				
Condition History			Wear	Oil	Cont.	Wear	Oil	Cont.	Wear	Oil	Cont.	Limit Name (Equipment / Oil) :				
												Comp Gas Nuovo Pignone, Preslia 32 (PTT)				
FocusLab ID	Test Method	Result	82904			76073			70812							
Date sampled			03-Sep-07			07-May-07			06-Feb-07							
Hours on Oil			Not Given			108187			Not Given							
Hours on Unit			110996			108187			106096							
Bottle ID			866183			854064			854095							
Wear Condition			RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	RDE fine		RFS coarse	
Wear Element	Method	Unit											U-Caution	U-Action	U-Caution	U-Action
Iron	D-6595	PPM	1.0	14.3	A	0.3	1.4		1.4	0.0		>2	>3	>4	>7	
Chromium	D-6595	PPM	0.4	0.3		0.0	0.0		0.0	0.0		>1	>2	>1	>2	
Lead	D-6595	PPM	0.7	1.0		0.0	0.2		0.0	0.0		>1	>2	>5	>8	
Copper	D-6595	PPM	0.3	0.7		0.3	0.2		0.2	0.2		>1	>2	>1	>2	
Tin	D-6595	PPM	0.7	0.0		0.6	1.0		0.0	0.0		>1	>2	>2	>3	
Aluminum	D-6595	PPM	0.1	0.0		0.0	0.0		0.0	0.0		>1	>2	>2	>3	
Nickel	D-6595	PPM	0.1	0.2		0.1	0.7		0.0	0.0		>1	>2	>1	>2	
Silver	D-6595	PPM	0.0	0.0		0.0	0.0		0.0	0.0						
Molybdenum	D-6595	PPM	0.0	0.0		0.0	0.0		0.1	0.0						
Titanium	D-6595	PPM	0.0	0.1		0.1	0.0		0.0	0.0						
Oil Condition			RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	L-Action	L-Caution	U-Caution	U-Action
Viscosity @40°C	D-445	cSt	32.1			33.0			32.7			31.7	<28.6	<30.1	>33.3	>34.9
Viscosity @100°C	D-445	cSt														
Oxidation	FTIR	Abs	2.3			2.3			5.3			5.0			>7	>9
Nitration	FTIR	Abs	2.7			2.5			4.0			3.0			>4	>6
TAN	D-974	mg KOH/g	0.11			0.13			0.12			0.14			>0.22	>0.3
TBN	D-4739	mg KOH/g														
Contamination			RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	RDE fine		RFS coarse	
Water	T-H2O Check™	% (Wt.)	0.009			0.014			0.011			0.013			>0.045	>0.076
Sodium	D-6595	PPM	0			0			0							
Silicon	D-6595	PPM	0.8	2.8		0.6	0.9		2.2	C	0.0		>2	>4	>3	>6
Additive Element			RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	RDE fine		RFS coarse	
Boron	D-6595	PPM	0			0			0							
Magnesium	D-6595	PPM	0			0			0							
Calcium	D-6595	PPM	3			0			1							
Barium	D-6595	PPM	0			0			3							
Phosphorus	D-6595	PPM	26			11			14							
Zinc	D-6595	PPM	2	19		1	5		2	2						
Additional Test			RDE fine		RFS coarse	RDE fine		RFS coarse	RDE fine		RFS coarse	New Oil	L-Action	L-Caution	U-Caution	U-Action
Flash Point	D-3828	°C										>				
Viscosity Index	D-2270															
Other																

Note: Alarm Limits are variable and dependent upon dataset size and to be used as general guideline.

No Sign or : NORMAL , or : CAUTION (first level warning limit) , or : ACTION required (second level warning limit)

U-Caution : Upper CAUTION Level L-Caution : Lower CAUTION Level

U-Action : Upper ACTION required Level L-Action : Lower ACTION required Level

Accuracy of interpretation and recommendation are based on representatives sample and information supplied

First level warning limit in Upper level and/or Lower level


Second level warning limit in Upper level and/or Lower level

No warranty is expressed or implied for this report.

Customer Code : 25001

Unit ID Number

: TEK 3200 Preslia 32



		Current Sample		Previous Sample			Alarm Limit Range					
FocusLab ID		82904		76073		70812		Limit Name (Equipment / Oil) :				
Date sampled		03-Sep-07		07-May-07		06-Feb-07		Comp Gas Nuovo Pignone, Preslia 32 (PTT)				
Hours on Oil		Not Given		108187		Not Given						
Hours on Unit		110996		108187		106096						
Bottle ID		866183		854064		854095						
Particle Count		NAS 1638: Number of Particles Per 100 Milliliter (Counts/100ml)					New Oil	U-Caution		U-Action		
Size Range	No. of Particles	Class	No. of Particles	Class	No. of Particles	Class	Class	No. of Particles	Class	No. of Particles	Class	
5-15 microns	116,400	9	29,800	7	54,500	8	<7	<8		<9		
15-25 microns	10,600	8 C	2,700	6	5,000	7						
25-50 microns	3,000	9	800	7	1,400	8						
50-100 microns	300	8	<100	6	100	7						
>100 microns	<100	7	<100	5	<100	6						
Particle Count		ISO 4406:1999: Number of Particles Per Milliliter (Counts/ml)					<1000		<1500			
Size Range	No. of Particles	Class	No. of Particles	Class	No. of Particles	Class						
>4 microns	3,491 A	19	894	17	1,635	18						
>6 microns	977	17	250	15	458	16						
>14 microns	137	14	34	12	64	13						
ISO 4406 Result		19/17/14		17/15/12		18/16/13						

Recommendations and Notes

Particle count indicates that oil cleanliness level is dirty. Suggest using an off-line filtration system to clean up the oil system.

Option Test: Varnish and Sludge Potential Index™ (VsPI™), Testing for Predicting Varnish and Sludge Buildup

		VsPI™ Severity Limit Range Guideline	
VPI™ Value		New Oil	
SPI™ Value		U-Caution	
VsPI™ Value		U-Action	
Sludge Weight Condition			
mg/100 ml			
mg/100 ml			
mg/100 ml			

Option Test: RUL (Remain Useful Life), Testing for monitoring Percent Remaining Anti-Oxidant (AO) by ASTM D-6971

		New Oil	
% Remaining Antioxidant Additive		U-Caution	
		U-Action	

Customer : 25001

Unit ID
Number


: TEK 3200 Preslia 32

Lube System Capacity : 9400 Liters


Location :

Wear Condition

RDE Fine Wear Metal




RFS Coarse Wear Metal




Oil Condition

Viscosity at 40 C in cSt






Viscosity at 100 C in cSt



Customer Code : 25001

Unit ID Number

: TEK 3200 Preslia 32



5-4 SERVICING

5-4.1 Oil Tank. Service lube oil storage tank per packager's manual.

5-4.2 Water Servicing and Pumping Requirements (NOx Suppression). For gas generators equipped with Nox suppression systems, refer to Chapter 4.

5-4.3 Compressor Efficiency Trending.

a. General. The efficiency of an engine is adversely affected by a contaminated (dirty) compressor section. Cleaning the compressor section can return the engine to a high efficiency condition. A procedure for monitoring engine performance over extended operating periods is provided in succeeding sub-paragraphs. The procedure encompasses the collection and correction of certain engine operating data and the plotting of this data on a curve. The results are then compared with like data obtained when the engine was in a new and clean condition. This comparison will aid the operator in determining when to clean the engine compressor section.

b. Compressor Condition Trend Curve.

(1) The establishment of a Compressor Condition Trend Curve may be useful in determining the efficiency of the compressor. This data may be useful in establishing an optimum wash interval.

(2) In formulating a compressor condition trend curve it is necessary that good baseline data be obtained when the particular engine is known to be in a clean condition. This baseline data is used to develop the initial zero-time point on the trend curve and is represented by the A° line on the sample curve in figure 5-52.

(3) In order to eliminate as many variables as possible, an attempt should be made to record all data points at approximately the same gas generator speed (± 100 RPM).

(4) Any adjustment or change made to the gas generator variable stator system will have an effect on gas generator performance parameters. If a variable stator system adjust-

ment is made, a new baseline curve must be established.

(5) A trend curve is valid only as long as the gas generator remains in the same installation, with the same instrumentation.


(6) The following operating data are suggested for monitoring the condition of the LM2500 engine compressor. These items should be recorded at a gas generator speed of 9000 RPM. Readings should be taken after a five minute stabilization period.

<u>Item</u>	<u>Units</u>	<u>Accuracy</u>
Discharge gas temperature (T5.4)	°F (°F=°C x 1.8 + 32)	$\pm 5^{\circ}\text{F}(\pm 3^{\circ}\text{C})$
Ambient temperature (Tamb)	°F	1°F (0.5°C)
Discharge gas pressure (P5.4)	psig (psig= kPa/ 6.89476)	$\pm 1/4\%$
Inlet Pressure (P2)	inches of water (inches = mm/25.4)	± 0.1 inch (2.54 mm)
Ambient pressure (Pamb)	inches of mercury (absolute)	± 0.1 inch (2.54 mm)

(7) Observed instrumentation readings must be converted to like units and corrected to standard conditions of pressure and temperature. The temperature correction factor is designated THETA (Θ) and the pressure correction is designated Pamb.

(a) Convert temperatures read in °C to °F, pressures read in kPa to psig, and pressures read in mm to inches per formulas in step (6).

(b) Calculate corrected gas generator discharge temperature as follows:



BLM2-1575-00-A2A

Figure 5-52. Sample Trend Curve of Discharge Gas Temperature at a Constant Pressure Ratio vs. Operating Time

1 In Table 5-30, opposite the ambient temperature (°F), find Θ (theta).

NOTE

If the ambient temperature is beyond the range of the Table 5-30, calculate Θ using the following formula:

$$\Theta = \frac{\text{Ambient temperature (°F)} + 460}{519}$$

2 Convert observed gas generator discharge temperature, °F to °R by adding 460.

3 Divide gas generator discharge temperature, °R by Θ .

(c) Calculate gas generator pressure ratio ($P5/P2$).

1 Convert observed ambient pressure (inches of mercury absolute) to P_{amb} (ambient pressure in pounds per square inch absolute) by multiplying observed reading (step (6)) by 0.49116.

2 Convert observed gas generator inlet total pressure (inches of water) to $P2$ (gas generator inlet total pressure in pounds per square inch absolute) by using the formula $P2 = P_{amb} - (\text{observed reading} \times 0.03613)$.

3 Convert observed gas generator discharge gas pressure (pounds per square inch) to $P5$ (gas generator discharge pressure in pounds per square inch absolute) by adding P_{amb} to observed reading.

4 Divide $P5$ by $P2$.

(8) Using corrected data developed in step (7), plot a curve of corrected gas generator discharge temperature against gas generator pressure ratio. See sample shown in figure 5-53.

(9) Establish performance analysis curve as follows:

(a) Select pressure ratio within range plotted in step (7)(c). This pressure ratio will be used throughout the performance analysis period.

(b) Establish curve of corrected gas generator discharge temperature against gas generator operating hours (figure 5-52).

1 Periodically, as determined by the engine operator, repeat this procedure.

2 Using new curve plotted per step (8), and the same pressure ratio used to establish the first point on the performance curve, plot the second, third, etc. points.

(10) At any time corrected gas generator discharge temperature has increased a total of 30°F (16.6°C) above initial temperature (clean condition temperature), it is recommended that the compressor be cleaned.